


A-4-165 ✓

MAP NO. _____ ELEV. 2898 DF
 STATE Kansas COUNTY Seward SEC. 2 Twp 35 S Rge 34 W
 OPERATOR Anadarko Production Company - Liberal, Kan Loc. C NE/4
 WELL NO. 1 FARM NAME Printz "A" FT. FROM _____ LINE
 Loc. Higdon (PD 2750) FT. FROM _____ LINE
 FR. 1-25-61 SPUD. 1-26-61 COMP. 4-10-61

CONT./GEOL. Capitt Drilling tools

NAME PRODUCING INTERVAL	COMPLETION RECORD FROM - TO	PERF. W/HOLES	TREATMENT RECORD
<u>Chase Group</u>	<u>2658-2738</u>	<u>76</u>	<u>5000 Ac</u>
b			
c			
d			



I. P. OIL/DIST.	WTR.	GAS	M.C.F.P.D.	CHK.	HRS.
a			<u>316</u>		
b		<u>(State deliverability test)</u>			
c					
d					

D & A ()

SIP#	FI TP #	FI CP#	SIBHP	
<u>342</u>				
GOR.	GR.	PBTD	TD	
		<u>2741</u>	<u>2760</u>	
SIZE	DEPTH	CASING - CEMENT RECORD W/SAX.	DEPTH	W/SAX.
<u>8-5/8"</u>	<u>691</u>	<u>400</u>		
<u>4 1/2"</u>	<u>2750</u>	<u>620</u>		

OPERATOR Anadarko Prod Co WELL NO. 1 Printz "A" ELEV. 2898 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
			<u>Herrington</u>	<u>2656</u>	
			<u>Krider</u>	<u>2692</u>	

Spud 1-26-61. 8-5/8" @ 691 w/400 sx.
 RTD 2760, logs. 4 1/2" @ 2750 w/620 sx. MIST, GO to 2741.
 P/10/2733-38. 500 Ac. Ga 139 MCF + 15 GAW/1 hr. 2500 Ac. 8
 hr ga 720 MCF + 20-30 GWPB.
 P/12/2718-24, 22/2695-2706, 32/2658-74. 2000 Ac. Ga 945 MCF +
 10 GSWPB fr (2658-2738). 30 min BD 3170 MCF dec to 2676 MCF/
 1 hr.

IP (State del. test) 316 MCF, SIP 342, fr Chester(2658-2738).
 COMPLETE 4-10-61