

WILDCAT

12-343W Map No. 12-83OPER AMARILLO NAT. GAS CO. & W.J. FELLERSAmarillo, TexasWELL #1-6 DOWDYR Mahoney Drlg.WC 1 1/2 mi W of Wide Awake Field (Tor & Miss)I.P. Cal OF 5,023,000 Cfgpd, Mrw 6231-36S-T-R 6-35S-34WSPOT NE NE SWCO SEWARD (Ks)ELEV 2950 KB

(KB Log)

Hb	4334	-1384
U/Tor	4348	-1398
Lan	4400	-1450
LKc	4454	-1504
Mar	5188	-2238
Cher	5556	-2606
Mrw	5893	-2943
Keyes	6210	-3260
Miss	6243	-3293
Ste G	6589	-3639
St L	6683	-3733
LTD	6725	-3775
RTD	6686	-3736

(KB Spl)

Hb	4310	-1360
RTD	6686	

DST #1 (KC) 4459-81, Op 1 hr, R 3'M, All press 0DST #2 (Mrw) 6230-67, Op 1 hr, GTS/1", Ga 100,000 Cfgpd
/1", Ga 258,000 Cfgpd/30", Flu rec NA, Press NARTD 6686' - Log - 4 1/2" @6400'

10/6231-36 (Mrw) NTN, 1000A, Ga 2,600,000 Cfgpd/NT,
SIP 1585/12 hrs, Frac (20,000 ga Diesel oil X 20,000# sd)
Pull swab 3 times & flo, Ga 6,000,000 Cfgpd thru 20/64"
Ck, FCP 1450# & FTP 1160#, 4 Pt Cal OF, 5,023,000 Cfgpd
SIP 1457# COMPLETED 12-28-65

4pt 12,750 mcf } from Mahoney
SIP 1655 }

3 3/4 B Diesel + Cond Ph.

Data Inc

at 400 B LTR

MISC DATA

GEOL _____

FTG _____

SUPPT _____

CSG 8" @1378 w/700 sx. 4 1/2" @6400ELEV 2948 DFSPUD DATE 11-24-65

DRLG COMP _____

FR by DATA 11-8-65COMP by " 12-29-65

L.S. 2949 E OF
2941 G.W.

LIBERAL ELECTRIC LOG TOPS

win

Heebner 4334 (-1384)

Toronto 4348 (-1398)

Lansing 4464 (-1514)

Marmaton 5206 (-2256)

Morrow 5892 (-2942)

"S-3" Sand 6208 (-3248) 6/30/68

6226 (-3276) 12 20

Chester 6278 (-3328)

Chester Ls 6296 (-3346)

Ste. Gen 6592 (-3642)

St. Louis 6658 (-3708)

Por 6684 (-3734 (18'))

TD 6686