

4-222W MAP NO. K-83

SEC. 5-35S-34W

STATE Kansas COUNTY Seward

LOC. C NE SE

OPER. W.J. Coppinger - Wichita, Kansas

FT/FR _____ LINE

WELL #2 FARM Long

LS

FT/FR _____ LINE


Wide Awake Field (Tor G & * ELEV. GR. 2936 DF 2939 KB

CONT. Mahoney Drilling Co., Inc. GEOL. Doug Marden

INT. *Miss O/C)

F.R. 3-1-65 SPUD 2-27-65 COMP. 4-22-65

TD. 6765 FM. St L PBTD. _____



Chester 6486-96½ 2/2000A & Frac

Flo 916 BOPD / tr wtr, Gr 52.2 deg

8-5/8" @1378' w/700 Sx. 4½" @6647' w/200 Sx.

Data Inc.

KB Spl Tops:)
 b 4296 DST #1 (Ches sd) 6472-6510, Op 1 hr, R
 /Tor 4344 1200' oil (no Gr) NW, ISIP 2162#/30", IFP 47#,
 /Tor 4387 FFP 292#, FSIP 2107#/30"
 ans 4448 DST #2 (St L) 6619-48, Op 90", R 15' V sli
 Chest 6399 GCM, ISIP 276#/30", IFP 15#, FFP 46#, FSIP
 Ches sd 6466 92#/30", RTD 6765, Ran Log, 4½" @6647' w/
 Ste G 6536 200 Sx., MICT 3-30-65, GRN Log, 6660-5850,
 L 6611 21/6486-96½ (Ches sd) 20 GMOPH w/SG/3 hrs
 6765 -3826 2000, 10% MCA, § 1d, § 5 BOPH-NW, Frac (20,
000 gell oil x 7250# sd x 500 walnut hulls)

KB Log Tops:)
 b 4301 -1362 MP 2800#, Ran 2-3/8" tbg, § 65 B 1d then
 /Tor 4350 -1411 flo all 1d, Flo 38 BOPH-NW thru ½" ck/4 hrs,
 /Tor 4391 -1452 FTP 220#, Flo 15-20 BOPH-NW thru 3/8" ck
 ans 4452 -1513 FTP 320#, State Pot: 4-14-65, Flo 916 BOPD
 Chest 6396 -3457 / tr W thru ½" ck, Gr 52.2 deg, Ches 6468-
 Ches sd 6463 -3524 96½ - COMPLETED 4-21-65
 Ste G 6525 -3586
 St L 6614 -3675
 LTD NA

LIBERAL ELECTRIC LOG TOPS

2939 KB

Winfield 2762 (+177)
Heebner 4328 (-1389)
Toronto 4348 (-1409)
Lansing 4464 (-1525)
Marmaton 5188 (-2249)
Morrow 5894 (-2955)
"S-3" Zone 6182 (-3243) *o/8*
Chester 6190 (-3251)
Sand 6484 (-3545) 14/30; ϕ 916 BOPD + tr wtr
Ste. Genevieve 6552 (-3613)
St. Louis 6632 (-3693)
TD 6765