


20015

12-55W Map No. 83

OPER MALLONEE-COPPINGER OPERATIONS, INC.
WICHITA, KS.

#5 LONG
CONTR MAHONEY DRLG. CO., INC.

FIELD WIDE AWAKE FIELD (MRW)
I.P. STATE POT: FLO 124 BOPD, NW, GR 40.4 DEG
MISS PFS 6486½-6503 API#15-175-20,015



S-T-R 5-35S-34W
SPOT APP C SE SE
CO SEWARD, KS.
ELEV 2936 KB

SPUD 10-12-67 8 5/8" 1393/650 SX GEOL - DOUG MARDEN

DST #1 (LAN) 4457-4482, OP 10" (PRE FLO) OP 60", R 330' WCM, ISIP 1277#/45", FP 61-168#, FSIP 1110#/45" (BHT 115 DEG)

DST #2 (LAN) 4193-4240, OP 25" (PRE FLO) OP 60", R 590' DM, BTM HALF ALL SW, ISIP 1662#/45", FP 37-140#, FSIP 1625#/45" (BHT 118 DEG)

DST #3 (CHES) 6487-6532 OP 15", (PRE FLO) OP 60", GTS/17" GA 44,000 CFGPD, R 750' FLU = 180' HOGCM + 300' FO + 270' SOGCM, ISIP 913#/45", FP 107-122#, FSIP 913#/45" (BHT 140 DEG)

RTD 6675, LOG 4" 6673/200 SX
MICT, CO, LOG, PF 28/6486½-6503 (CHES), 2000/MCA (10%)
§ DN, NO TST, RE-PF 15/6486½-6503 (CHES) § DN, FRAC 20,000 GAL
CELL DIESEL OIL + 100 BBLs LEASE OIL + 10,000# SD, § LD
LD, FLO 4 BOPH, 20/64" CK FLO 8 BOPH ON 46/64" CK
STATE POT: FLO 124 BOPD, NW, GR 40.4 DEG, MISS PFS 6486½-6503
COMPLETED 12-6-67

KB LOG TOPS
HB 4299 -1363
U/TOR 4346 -1410
L/TOR 4389 -1453
LAN 4453 -1517
MAR 5148 -2212
CHER 5550 -2614
MRW 5889 -2953
MISS-CHES

6206 -3270
L/CHES 6463 -3527
STE G 6528 -3592
ST L 6619 -3683
LTD 6675 -3739

KB SPL TOPS
LAN NOT CALLED
MAR 5153 -2217
CHER 5549
MRW 5887
CHES SD 6484
STE G 6532
ST L 6618
RTD 6675

MISCEL DATA
GEOL DOUG MARDEN
FTG _____
SUPPT _____
CSG 8" 1393/650 SX 4" 6673/200 SX
ELEV 2934 DF
2926 GR

SPUD DATE 10-12-67
DRLG COMP _____
FR by DATA 10-11-67
COMP by " 12-7-67