
State Ks. Field W.C. Wide Awake
 Company Weathoma County Seward
 Farm Long No. 1

Sec. 5 Twp. 35 Range 34

Spot 680' N + 600' E of C


Contractor Mid Western Dr

Remarks 6500 Miss

Comm. 10-14-58 Comp. 5/24/59

Elev. 445 DF 2934 GI 2927 KB 2937 TD 6550 PB 6522

Pay Ches. 6470 - 6512 overall



I.P. P 71 BOPD Press.

Casing Record: 13 3/8 652/550 7"

20" 10 3/4 5 1/2" 6548/900

16" 9 5/8 2898/600

	Sample	Log
TTD 654	U Tor 4348	U Tor -1411 4345
running csg.	L " 4385	L " -1451 4385
OCT 22 TTD	Lan 4460	Lan -1523 4457
2900 w, WOC	Mar 5865	Mar 5158
OCT 29 E 4386-4406		Choro 5522
rec 20' 14' 1s bldg,		Mar -2928 5862
6' sh, DST 4388-		Miss -3245 6179
4406 op 1' gts 35"		Ches -3535 6469
totm rec 10' hgcm		" 10' 79
FP 30-30 BHSIP 1255/20		" 55 -3558 6492
44643		" 4' 6501
NOV 5 4 6051		" 55 15 -3571 6505
NOV 12 E 6204-21 1/2		" 14' 19
rec 16 1/2' 6' 1s N.S. 3" sh, 3' 3" 1s		
N.S. 2' 6" sh, 6" 1s N.S.		
E 6221 1/2 - 32 1/2 rec 10', 9' sh 9" 1s		
N.S. 3" sh DST 6462-6505		
op 1' gts 22" totm rec 180' free oil		
90' m oil 240' hot gcm FP		
67-129 SIP 1731/20 RTD 6550, logs,		
(over)		

Cag WOCT

NOV 19

CO. 6522 C/R

P 35/6493 - 6500 ✓

25/6507 - 12 A₂/1000 m

sub 4 B0/2' gas tst m

FX 15 (gal H₂O) x 7.5 sd

subg.

NOV 25

sub^{sub} 1d 137 B0 + 32 Bw/16'

p1 @ 6486 P 35/6470 - 77

A/1000 m sub 30.52 B0 +

7 Bw/06' dr p1 to bot. sub

55 B0 + 600 1d x wtr/24' swbs

DEC 3

MOCT POP

DEC 10

DEC 17

DEC 30

JAN 7

JAN 14

JAN 21

JAN 28

FEB 4

FEB 11

FEB 18

MAR 4

MAR 11

MAR 18

MAR 25

APR 1

APR 8

APR 15

APR 22

APR 29

MAY 6

MAY 13

MAY 20

MAY 27

st. tst

P 71 B0

(w/wtr.) about 50%?

Cher ss 6470 - 6512 overall

AMARILLO TOPS

2937 KB

win 2760 + 174

Heebner 4323 (-1386)

Toronto 4345 (-1408) tst'd gas TSTM

Lansing 4457 (-1520)

Marmaton 5158 (-2221)

Morrow 5860 (-2923) T 318', no sand

Chester 6178 (-3241) gas TSTM

"C-2" sd 6468 (-3531) 32/34 brkn, IPP 71 BOPD + wtr

St. Gen 6526 (-3589)

TD 6550

st Lo 6596 - 36.64 @ 100 B0

See other ticket for Deepening