

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


5-35-35W

Company- TEXACO, INC.  
Farm- E.E. Jennison No. 2

SEC. 5 T. 35 R. 35W  
C NW SE

Total Depth. 6783'  
Comm. 2-7-64 Comp. 3-28-64  
Shot or Treated.  
Contractor. D & M Dlr. Co.  
Issued. 6-6-64

County Stevens  
KANSAS



Elevation. 2990' G.L.

CASING:  
8 5/8" 1675' w/450 sx cem.  
4 1/2" 6348' w/125 sx cem.

Production. 4247 MCFG & 14 B.  
cond Per MCFG 45 Hr. SIP  
1626#

Figures Indicate Bottom of Formations.

sand, shells	1675
shale, shells	1755
shale	2360
shale, lime	3143
shale	3223
shale, lime	3645
shale, chalky lime	3875
lime, shale	3942
shale	4067
lime, shale	4941
lime	5118
lime, shale	5300
lime	5428
cherty lime	5479
lime	5560
shale	5750
shale, lime	5882
shale	6225
shale, lime	6563
shale, sand	6726
lime	6783
Total Depth	

TOPS: SCOUT	
Neva	3284
Topeka	3973
Toronto	4338
Lansing	4454
Kansas City	4902
Marmaton	5212
Cherokee	5464
Morrow	5894
Morrow sand	6274-79
Morrow sand	6296-6312
Mississippi Chester	6337
St. Genevieve	6610
St. Louis	6774