

6-35-35W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - TEXAS COMPANY
Farm D. L. Haworth No. 1

SEC. 6 T. 35 R. 35 W
SE 6 NW
2526' FNL 2551' FWL NW 1/4

Total Depth. 2822'
Comm. 10-2-45 Comp. 11-6-45
Shot or Treated. Acidized
Contractor. Kiowa Drlg. Co.
Issued. 2-23-46

County. Stevens
KANSAS



Rotary 0-2700'
Cable 2700-2822'

CASING:
10 3/4" 716' Cem.
7" OD 2699' Cem.

Elevation. 3011 ft

Production. 21,996,000 Gas.

Figures Indicate Bottom of Formations.

surface sand & clay	455
sand & clay	640
red bed	1340
sand & lime	1412
sand	1432
sand & red bed	1720
red bed	1892
lime sdy	1898
shale & lime	2062
lime	2076
lime & shale	2215
lime	2234
lime & shale	2264
lime	2290
anhydrite	2316
lime	2558
lime & shale	2582
lime	2610
lime & shale	2646
lime	2712
lime & shale	2718
lime gy	2750
lime	2768
lime blue	2774
shale & lime	2812
lime hrd	2822
Total Depth.	

gals. 15% acid. - no press.
acidized in 14 min. Well
tested 5,400,000 cu. ft. gas.
The hole was then swbd &
dried up & tested without
shutting in. Tested 6,750,000
cu. ft. Acidized again w/12,000
gals. w/5% acid, then pumped
3,500 gals. wtr. on top
12,000 gals. acid. Shut in well
48 hrs. - opened 20 min. - tested
20,572,000 cu. ft. gas. shut well
in again for 72 hrs. - Opened
20 minutes - tested 21,996,000
cu. ft. gas.

Tops:
Hollenberg 2666
Herrington 2700
Krider 2717
Winfield 2783

Run Schlumberger Survey @
2638'

Run 120' of 5 1/4" Perf. Liner
set @ 2822' - Perf. 100'
from btm up.

Acidized w/4000 gals. 15% acid.
used 300 gals wtr to flush
acid. Acidized again w/8000