

7-35-35W

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company TEXAS COMPANY
Farm L. D. Goosh No. 1

SEC. 7 T. 35 R. 35 W
NW 1/4 SE
2605' fEL & 2605' fSL, 35' E
& 35' S of Center of Sec.
County. Stevens.
KANSAS

Total Depth. 2870'
Comm. 10-31-45 Comp. 11-14-45
Shot or Treated. Acidized
Contractor. Kiowa Drlg. Co.
Issued. 1-5-46

CASING:
10 3/4" 677' Cem. LI
7" OD 2860' Cem. LI



Elevation. 2013.2h

Production. Open flow 20,712 MCF
R. P. 430#

Figures Indicate Bottom of Formations.

surface clay	135
sand & clay	650
red bed	680
red bed & sand	1404
shale & shells	1706
lime	1732
lime & shale	1936
lime	1964
lime & shale	2078
lime	2116
lime & shale	2214
shale	2246
lime & shale	2386
lime	2870
Total Depth.	

Tops:
Blaine 1010
Stone Corral 1669
Hollenberg 2672
Herrington ?
Krider 2720
Winfield 2783
Ft. Riley 2843

Perf. 2783-2822' - 234 holes 3/8" size.
Then acidized w/300 gals. 15% acid.
Perf. 2721-71' - 300 holes 3/8" size. Acidized again w/1000 gals. 15% acid w/6000 gals. wtr. load.
Max. press. 390#. Shut in well for 12 hrs. & then tested 10,261,000 cu. ft. gas. Acidized again w/12,000 5% acid, then swbd & dried up hole. Shut well in 18 hrs. & after 20 min. blow down, well tested 16,183,000 cu.ft. gas. Swbd hole again, then shut well in again for 12 hrs. - tested 14,183,000 cu.ft.gas. Shut well in 72 hrs. & then opened 20 mins., well tested 20,712,000 cu.ft. gas.