

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


7-35-35W

Company- Texaco
Farm- Gooch Unit No. 2

SEC. 7 T. 35 R. 35W.
C SE NE

Total Depth. 6654
Comm. 5-2-64. Comp. 6-11-64
Shot or treated.
Contractor. Arrow Drilling Co.
Issued. 10-31-64

County Stevens
KANSAS



Elevation. 3008 KB

CASING:

8 5/8": 1707 w/ 425sx.
5 1/2": 6654 w/175sx.

Production. FLO 249 BOPD
& 2477 MCFGPD

Figures Indicate Bottom of Formations.

Surface Clay-Sand	650
Red Bed-Sand	1083
Shale-Anhydrite	1707
Clay-Sand	1897
Shale	2548
Shale	2748
Shale - Lime	3101
Shale	3344
Lime-Shale	3956
Lime	4116
Lime-Shale	4231
Lime	4316
Lime-Shale	4560
Lime	4690
Lime-Shale	5076
Lime	5380
Lime-Shale	5723
Shale	6086
Shale-Lime	6573
Shale	6586
Shale-Sand	6626
TOTAL DEPTH	

TOPS

Toronto	4346
Lansing	4463
Kansas City	4920
Base Kansas City	5130
Marmaton	5218
Morrow	5942
Morrow Sand	6284
Brown Morrow Sand	6384
Chester	6360
Chester Sand	6602
St. Geneva	6638

LOGS RUN: Induction-Electric, Sonic, Dipmeter, Neutron Correlation