


Company- TEXACO INC.
 Farm- T.R. Gooch Unit No. 2

SEC. 8 T. 35 R. 35W
 C SE NW

Total Depth. 6978'
 Comm. 9-3-63 Comp. 9-19-63
 Shot or Treated.
 Contractor. Noble Drilling Co.
 Issued. 12-28-63

County Stevens
 KANSAS



Elevation. 2980' GL

CASING:
 8 5/8" 1696' cem w/425 sx.
 5 1/2" 6963' cem w/60 sx.

Production. 11,291,000 CFG +
 6B/DIST/MMCFG (Morr.
 Sand-6266-6325)
 175 BOPD, 3. BW (Chest
 Zone 6570-75)

Figures Indicate Bottom of Formations.

redbed, shale, sand	1001
sand-shale	1610
Anhydrite	1696
Anhydrite-shale	1818
Anhydrite, shale, redbed	2215
shale & lime	2415
lime	2600
lime & shale	2784
not shown	2803
lime	3091
lime & shale	3232
lime	3610
lime & shale	4074
lime	4286
lime & shale	4416
lime	4571
lime & shale	4947
lime	5088
lime & shale	5952
shale	6283
lime & shale	6490
lime	6583
not shown	6584
lime	6638
lime & shale	6688
lime	6914
not shown	6936
lime	6950
lime ?	6978 RTD
Total Depth	

TOPS: LOG

Council Grove (sample)	2980
Neva	3290
Topeka	3967
Toronto	4340
Lansing	4459
Kansas City	4917
Marmaton	5217
Cherokee	5474
Morrow	5926
Morrow Sand	6266-90
" "	6306-25
Chester	6355
Chester Sand	6570-6604
St. Geneva	6638
St. Louis	6812
Sperg	6954