


Company- TEXACO
 Farm- M. Fields Unit No. 2

SEC. 9 T. 35 R. 35W
 75' NW / C NE SW

9 - 35 - 35W

County Stevens
 KANSAS



Total Depth. 6602'
 Comm. 3-18-65 Comp. 4-4-65
 Shot or Treated.
 Contractor. Garvey Drilg.
 Issued. 6-19-65

CASING:

8 5/8" 1678' cem w/ 765 sx
 4 1/2" 6447' cem w/ 125 sx

Elevation. 2985' KB

Production. 16,000,000 CFG
 12 Bbls Cond pd

Figures Indicate Bottom of Formations.

clay & sand	635
red bed	778
red bed & sand	1365
shale & Gyp	1668
anhydrite	1678
anhydrite & shale	1740
shale & shells	2385
shale & lime	2690
lime & shale	2800
lime w/ chalk	2980
lime & shale w/chalk	
strks	3125
lime	3165
shale, lime & chalk	3331
shale & lime w/chalk strks	3494
shale & lime	3605
lime, shale & chalk	3860
lime & shale	4463
lime	4536
lime & shale	4746
lime	4794
lime & chalky strks	4932
lime & shale	5225
lime	5306
lime & shale	5488
lime	5571
lime & shale	5651
shale & lime	5935
shale	5998
shale & lime	6260
lime & shale	5365
lime	6455
lime & shale	6592
lime	6602 RTD
Total Depth	
Tops: SCOUT	
Lansing	4463
Kansas City	4899
Marmaton	5208
Fort Scott	5483
Cherokee	5547
Morrow	5925
Morrow sand	6275
Morrow sand	6292-6303
Chester	6362
Chester sand	6576