12-35-35W

KANSAS DRILLERS LOG

S. 12 T. 35 R. 35 (W)

API No. 15 — 189 (County) — 20437 (Number)

Loc. C NE¼

County Stevens

640 Acres



Locate well correctly

Elev.: Gr. 2952'

DF _____ KB 2957'

Operator	Damson Oil Corporation
Address	3033 NW 63 #150-E, Oklahoma City, Oklahoma 73116
Well No.	1
Lease Name	Mudd Trust
Footage Location	1320 feet from (N) ~~(S)~~ line 1320 feet from (E) ~~(W)~~ line
Principal Contractor	Sage Drilling
Geologist	
Spud Date	Feb. 1, 1979
Total Depth	6475'
P.B.T.D.	6429'
Date Completed	Feb. 24, 1979
Oil Purchaser	N/A

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface Casing	12¼"	8 5/8"	24	1711'	Dowell LiteWt	600	¼#/sx F.S.+2%C.C.
					Class H	200	3% C.C.
Prod. Casing	7 7/8"	4½"	10.5	6474'	Class H	150	10% Salt

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement

TUBING RECORD

Size	Setting depth	Packer set at
2 3/8" EUE	6344'	

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
2		6346' - 6360'

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1000 Gal. clean-up acid	6346' - 6360'
12000 Gal. West Pad "A", 12000 Gal. Series 70 Type, 15% Acid	6346' - 6360'

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
Feb. 24, 1979	Flowing

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	0 bbls.	1012 MCF	0 bbls.	CFPB

Disposition of gas (vented, used on lease or sold)	Producing interval(s)
Sold - Northern Natural	Chester - 6346' to 6360'

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

C-10-1972

Operator		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Damson Oil Corporation		
Well No. 1	Lease Name Mudd Trust	Gas
S 12 T 35 R 35 E/W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Chase Gp. (Lime)	2716	3012	Chase	2716
Council Grove (Lime) Slight Show gas, wet	3042	3242	Council Grove	3042
Marmaton Show of oil and gas in mud, no tests	5238	5256	Lansing	4466
			Cherokee	5696
Lower Morrow Sand Tight, slight show of gas, no tests	6266	6294	Morrow	5934
Chester	6294		Chester	6294
Chester Porosity Productive - IPF 1012 MCFPD	6342	6362	TD	6472

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Stanley DeLong
Signature

Petroleum Engineer
Title

March 19, 1979
Date