

PL

12-35-35W

State Geol Survey  
WICHITA DIVISION

### KANSAS DRILLERS LOG

S. 12 T. 35S R. 35 W  
Loc. C NW/4  
County Stevens

API No. 15 — 189 — 20450  
County Number

Operator  
Damson Oil Corporation

Address  
3033 NW 63 Suite 150E Oklahoma City, OK 73116


Well No. 2 Lease Name Mudd Trust

Footage Location  
1320 feet from (N) (S) line 1320 feet from (E) line

Principal Contractor Sage Drilling Geologist

Spud Date May 15, 1979 Total Depth 6470' P.B.T.D. 6421'

Date Completed June 4, 1979 Oil Purchaser N/A



Elev.: Gr. 2948'  
DF 2953' KB 2955'

### CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface Casing	12 1/4"	8 5/8"	24	1700'	Lite Weight	600	1/2#/sx flo seal
					Class H	200	1/2#/sx flo seal
Production Casing	7-7/8"	4 1/2"	10.5	6469'	50-50 POS	400	2% GEL 18% salt 12 1/2# Kolite/sx

### LINER RECORD

### PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	Tornado Jet	6298'-6303'
			2	Tornado Jet	6361'-6367'

### TUBING RECORD

Size	Setting depth	Packer set at
2-3/8" EUE	6267	-

### ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
10,000 Gal 15% NE-HCl Acid plus 10,000 Gal gel water pad	6298'-6367'

### INITIAL PRODUCTION

Date of first production June 14, 1979 Producing method (flowing, pumping, gas lift, etc.) Flowing

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	-	1,083 bbls.	-	-

Disposition of gas (vented, used on lease or sold) Sold Producing interval(s) Chester-6298' to 6367'

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 N. Water, Wichita, Ks. 67202, 315-263-3238. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 2	Lease Name Mudd Trust	Gas
S 12 T 35S R 35 W		


**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
WINFIELD	2770		DIL	1700-
COUNCIL GROVE	3033		Compensated Density Neutron	6470
LANSING	4450			
CHEROKEE	5696			
MORROW	5952			
CHESTER	6336			
DST	6296	TD 6470		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Signature
	Engineer Title
	June 18, 1979 Date