

13-35-35W

## KANSAS WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY PLAINS NATURAL GAS CO.

SEC. 13 T. 35 R. 35W

FARM Farley

NO. 1

LOC. SE SE NW

125' N &amp; W of Center

TOTAL DEPTH 2759

COMM. 7-28-50

COMP. 8-9-50


SHOT OR TREATED Acid 26,000

CONTRACTOR

ISSUED 4-21-51

COUNTY Stevens

KANSAS



## CASING

10 3/4" 409' cem. w/200 sx  
 7" 2729' cem. w/623 sx

ELEVATION 2960 Ind.  
2959 DF

PRODUCTION 769,000 gas

## FIGURES INDICATE BOTTOM OF FORMATIONS

|                        |      |
|------------------------|------|
| clay, sand             | 400  |
| clay                   | 680  |
| red rock               | 940  |
| red rock, sand strks   | 995  |
| gyp                    | 1090 |
| sand, shale            | 1270 |
| red rock, gyp          | 1640 |
| gyp, shale, anhydrite  | 1820 |
| shale, anhydrite       | 1995 |
| shale, shells          | 2125 |
| shale, anhydrite       | 2500 |
| lime, shale, anhydrite | 2585 |
| anhydrite, shale       | 2640 |
| lime, shale, anhydrite | 2740 |
| lime                   | 2759 |
| Total Depth            |      |

## Scout Tops:

|              |      |
|--------------|------|
| Hollenberg   | 2614 |
| Herington    | 2679 |
| Upper Krider | 2710 |
| Lower Krider | 2734 |