

18-35-35W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - THE TEXAS CO.
Farm - C.A. Adamson No. 1.

SEC. 18 T. 35 R. 35 W
SWc NE
100' N 35' E of Cen.

Total Depth. 2875 PB 2806
Comm. 12-26-45 Comp. 1-13-46
Shot or Treated.
Contractor. Kiowa Drilg. Co.
Issued. 3-16-46

County. Stevens
KANSAS



CASING:
10 3/4" 687' LI Cem.
7" 2859' LI Cem.

Elevation. 3009 ft

Production. Open Flow 15,612,784 G
S.I.P. 425#

Figures Indicate Bottom of Formations.

surface clay	45
sand, shells & clay	490
sand & clay	650
red bed	695
shale & red bed	750
sand & red bed	1642
lime & shale	1700
red bed & shale	1740
lime & shale	2230
lime	2280
lime & shale	2395
lime	2430
lime & chalk	2480
lime	2514
lime & shale	2555
lime	2635
lime & shale	2675
lime	2875
Total Depth	

Plug Back 2806

Tops:

Blaine	?
Base Blaine	955
Stone Corral	1640
Hollenberg	2664
Krider	2713
Winfield	2774
Ft. Riley	2830

Run Schlumberger @ 2875
Perf. Winfield from 2776-
2806 - 180 3/8" holes.
Shut well in 12 hrs.
open 20 mins. Well tested
280,000 cu.ft. Gas.
Acidized w/3000 gals 15%
acid Max. press. 400#.
Swbd hole-open flow

then swbd wtr & there was no decrease in wtr. Drld cement & perf. from 2806-16 - 12 holes per foot 120 holes 3/8". Killed well & run plastic. Plugged back from 2831-18 w/ sand & run 17 gal. plastic - no fill up. Run 17 more gals. of plastic but no fill up. Had to kill well again to run more plastic. Dumped 60 gals of plastic with a 1" stream of wtr at the same time. Dumped 5' of Ottawa sand w/2' fill up, dumped 5 gals plastic with filler and got 1' fill up. Dumped 5 gals. plain plastic w/no fill up. Dumped 7 gals. plastic with filler & got 2' fill up or P.B. to 2806. Shut well in 24 hrs. before starting to swab. Swbd acid, water, mud & foam. Shut well in 12 hrs. opened up and blowed down 1 hr. before any moisture showed up. Shut well in 72 hrs. opened 20 mins. - Well tested 13,647,000 cu.ft. Gas. State test meter press. 346#. Shut well in 72 hrs. opened 20 mins. well tested 15,612,784 cu.ft. Gas. Shut in press. 425#.

test was 3,375,000. Swbd up & dried up hole. Shut well in 12 hrs. 20 min. blow down well tested 5,900,000 cu.ft. Gas in Winfield. Perf. Krider from 2716-62 w/ 276 holes 3/8" - Acidized w/10,000 gals 15% acid After acid open flow 6,800,000 cu.ft. Gas. Shut well in 12 hrs. opened 20 mins. Well tested 11,900,000 cu.ft. Gas. Acidized again w/ 12,000 gals. 5% acid.