

90060

3-387W

MAP NO. 83

SEC. 5-35S-35W

STATE Kansas COUNTY Stevens

LOC. C NW SE

OPER. Texaco, Inc., Wichita, Kansas

FT/FR 2002 LINE

WELL #2 FARM E. E. Jennison

FT/FR 2-S LINE

POOL Gooch Ext.

ELEV. 2990 GR. 2997 DF. 3000 KB

CONT. D. & M. Drlg. Tools

GEOL.

INT. 6675' test

F.R. 2/3/64 SPUD. 2/8/64 COMP. 3/24/64

TD 6784 FM. St Louis PBT. 6320

Completion Record

PRODUCING FM. FROM — TO PERF W/HOLES TREATMENT

Morrow 6274-6301 18 Frac

I.P. 4 Pt. Ga; 4,247,000 Cfgpd + 14 B Cond/per million

Casing Record

8-5/8" @ 1675' w/635 sx.

4 1/2" @ 6348 w/125 sx.

Data Inc.

KB Log Tops:

Neu	3284	- 284	Cher	5464	-2464	Ches	6337	-3337
Top	3973	- 973	Mrw	5894	-2894	St Gen	6610	-3610
Tor	4338	-1338	sd	6274	-3274	1st LTD	6688	-3688
Lans	4454	-1454	B/sd	6279	-3279	St. Lou	6774	-3774
Kc	4902	-1902	sd	6296	-3296	2nd LTD	6784	-3784
Mar	5212	-2212	B/sd	6312	-3312	RTD	6783	-3783

Q #1 (Ches) 6563-81, R 15' Sh + 3' lost

No DST's, Drld to 6690, Ran log to 6688, DD 6783 RTD, Ran 2nd log to 6784 TD, 4 1/2" @ 6348 w/125 sx., MICT, CO 6320 PBT, Ran corr log, Pf Mrw sd 8/6274-78 & 10/6296-6301, test for 1 hr. & Ga 50,000 Cfgpd, Frac (15,000# sd x 15,000 crude x 850# adomite x 500 gal 15%A + 10 Ball sealers) MP 3150#, Inj. 35.2 BPM @ 2900# Flo 20 BLO, NW/1 hr., \$ 9 BLO, NW/2nd hr., \$ & Fl 219 BLO, NW/24 hrs, Ga 2,530,000 Cfgpd, NW on pitot tube w/700# back pressure thru 20/64" ck, SI, WO 4 Pt test, Completed (3/10/64) Ga 4,247,900 Cfgpd + 14 B cond per Mmcfg, NW, 45 hr., SIP 1626# Mrw 6274-6301, COMPLETE (3/17/64)

LIBERAL ELECTRIC LOG TOPS

3000 KB

Morrow 5913 (-2913)

B "S-3" Zone 6222 (-3222)

C "S-3" Sand 6272 (-3272) 5/7; ϕ COF 4,247 MCF + 14 BCond/MMCF

D "S-3" Sand 6295 (-3295) 3/7

Chester 6312 (-3312)

Chester Sand Zone 6540 (-3540)

Ste. Geneviève 6610 (-3610)

TD 6690

Win 2766 + 234

Hb 4316 + 1316

Top 4338 - 1338

Lowr 4452 - 1452

MVM 52 10 - 2210