

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

4-35-37W

Location. Center NE $\frac{1}{4}$

Sec. 4 T.35 R.37W

Drilled with Rotary & Cable.

Casing Record.

County Stevens

20" 85/8 2550

Farm. Wiley

No. 1

15 $\frac{1}{2}$ " 65/8"

Company. The Argus Production Co.

12 $\frac{1}{2}$ " 682 53/16"

Contr. Garden Bros & Lippa Drlg.


Total Depth. 2830

Comm. 7-25-30

Comp. 9-13-30

Correspondence Regarding This Well Should Be Referred To.

Shot Quarts Between.



OCT 13 1930

Elevation

Figures ¹ indicate Bottom of Formations.¹ initial Production.

Date Issued. 10-11-30

4,305,828 Cuft G.

Formation

Depth.

surface sand

380

sand and shale

650

red rock

690

sand red bed and gyp shells

970

sdy red bed and gyp shells

1279

sand and gyp shells

1455

red rock and gyp

1541

red bed and gyp shells

1670

hard sand and lime

1724

broken lime

1744

lime hard

1770

broken lime

1800

sdy red bed and lime shells

1832

red bed and gyp shells

2128

gyp and red bed

2154

broken lime and gyp

2191

lime and red bed

2211

gyp

2226

gyp and red bed

2260

red rock and gyp

2270

red rock blue shale and lime

2288

shale blue

2294

shale blue

2302

broken lime and blue shale

2331

broken lime and shale

2357

lime

2375

broken lime

2378

broken lime and shale

2408

lime

2424

shale and shells

2446

broken lime and shale

2470

lime and shale

2480

lime

2497

broken lime and anhydrite

2534

lime brown

2539

anhydrite

2542

lime grey

2550

lime

2565

shale

2570

lime

1st gas 2690

2730

shale blue

2740

broken lime

2775

shale

2785

red bed

2800

sdy lime

2810

shale

2830

T.D.

Argus Prod. #1 Wiley
 Sec. 4-35-37W Can NE $\frac{1}{4}$
 Comm. 12-17-41 Comp. 3-18-42
 348' 1" of 7" liner
 1" perf. 2550-2871
 130 equals 2836 SLM
 Drilled deeper to 2871
 Prod. 2,586 MCF