


County. Stevens 11-35-37W

KANSAS



Total Depth. 2875'
 Comm. 4-15-48 Comp. 5-28-48
 Shot or Treated. Acidized
 Contractor. Moran Bros., Inc.
 Issued. 8-7-48

CASING:

10-3/4" OD 690' Cem.
 7" 2662' KB Cem.
 5-9/16" 2647'

Elevation. 3113 Ind.

Production. Open Flow:
 27,917,000 Gas

Figures Indicate Bottom of Formations.

surface, sand & clay 0-283
 sand & red bed 680
 red bed 740
 red bed & sand 1548
 shale & gyp 2397
 gyp, shale & anhy. 2458
 gyp & anhydrite 2621
 lime & gyp 2668
 broken formation 2674
 lime 2704
 lime stly hrd 2706
 lime 2710
 shale 2725
 lime 2768
 shale 2775
 shale red 2776
 lime 2820
 shale red 2835
 lime 2875
 Total Depth

Tops:
 Sandy Herington 2651
 Kln Herington 2662
 Krider 2723
 Winfield 2876
 Ft. Riley 2834

Gas Log:

First Gas	2706	Show
Increase Gas	2706-2740	647 MCF
"	2740-2747	457 "
"	2747-2754	792 "
"	2754-2760	915 "
"	2760-2775	1,121 "
"	2775-2782	1,022 "
"	2785-2800	915 "
"	2800-2810	2,743 "
"	2810-2818	2,918 "
"	2818-2835	2,884 "
"	2835-2850	2,959 "
"	2850-2865	2,663 "
"	2865-2875	3,034 "

Well was treated June 8th, 11th and 14th, 1948 with 18,000 gallons of 15% acid and 4,000 gallons of 7½% acid. Well gauged 27,917 MCF after acid on 20 minute open flow, 72 hour shut in.