

IMPORTANT
Kans. Geo. Survey request
samples on this well.

4-35-38W

KANSAS DRILLERS LOG

S. 4 T. 35 R. 38 ^EW
Loc. C NE
County Stevens

API No. 15 — 189 — 20,385
County Number

Operator
Kansas Petroleum, Inc.

Address 100-200 E. First Wichita, Kansas 67202


Well No. #1-A Lease Name Breckheisen

Footage Location
1320 feet from (N) ~~X~~ line 1320 feet from (E) ~~X~~ line

Principal Contractor Sage Drilling Co. Geologist None

Spud Date 2/15/78 Total Depth 3130 P.B.T.D. -

Date Completed 2/20/78 Oil Purchaser



Locate well correctly
Elev.: Gr. 3207

DF - KB 3212

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8"		602'	Pozmix	400	2% CC
Production	7 7/8	5 1/2	14#	3130	Pozmix	650	18% Salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
None					

Size	Setting depth	Packer set at
1 1/2	3116	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
2500 Gallons 15% MCA	
2680 Bbls. of Salt Water and 150,000# Sand	2952-3068

INITIAL PRODUCTION

Date of first production <u>3/10/78</u>	Producing method (flowing, pumping, gas lift, etc.) <u>Pumping</u>
RATE OF PRODUCTION PER 24 HOURS	Oil bbls. <u>750 MCF</u> Gas <u>40</u> bbls. Water Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval(s) <u>2952-3068</u>

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Kansas Petroleum, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Gas
Well No. #1-A	Lease Name Brecheisen	
S 4 T 35 R 38 E W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand and Clay	0	100		
Sand and Red Bed	100	610		
Red Bed and Gyp	610	1130		
Sand and Shale	1130	1520		
Shale	1520	2610		
Lime and Shale	2610	3130		
5 1/2" set @ 3127' w/650 sax cement				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Signature
	James Tasheff President
	Title
	January 23, 1979 Date