

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

500 East Murdock,

Wichita, Kansas

9- 35- 38W

Company- NORVAL BALLARD

Farm- Brecheisen

No. 1

SEC.

9

T.

35

R. 38W

CSW

Total Depth. 2829 SLM

Comm. 11-25-51

Comp. 12-17-51


Shot or Treated.

Contractor. Walter Kuhn Drlg. Co.

Issued. 5-31-52

County Stevens

KANSAS



CASING:

8 5/8" 700' cem. w/225 sx circ.

5 1/2" 2808' cem. w/450 sx

Elevation. 3226 KB

3216 (2nd)

Production. 19,009,000 Gas

Figures indicate Bottom of Formations.

surface sand & clay	450
shale blue & sand	500
shale blue & gyp	650
red bed	750
sandy red bed	1070
red bed & gyp	1160
red rock & sand	1450
red bed & red rock	1730
anhydrite & shale	2645
lime	2695
lime & shale	2760
lime	2830
Total Depth	2829 SLM

Tops:

Herington	2625
Krider	2673
Winfield	2739
Ft. Riley	2806

SLM 2829:

Perforated 4 holes per ft.

2654-60' in Herington

2675-2732 in Krider

2739-45' in Winfield

2748-82 in Winfield

Acidized w/20,000 gals. of acid.

Initial production on 72/20 was
19,009,000 cubic feet with 349#
shut-in pressure.

Initial deliverability test commenced 3-28-51
" " was 3,099,000 cubic feet
with a shut in pressure of 367.6#.

Elevation 3221 ground,