

WELL COMPLETION REPORT AND DRILLER'S LOG

API No. 15 — 129 — 20,485
County Number

Operator

Anadarko Production Company

Address

P. O. Box 351, Liberal, Kansas 67901

Well No.

1

Lease Name

LIGHT "J"

Footage Location

1250 feet from (N) ^{XX} line 1250 feet from (E) ^{XX} line

Principal Contractor

Gabbert-Jones, Inc.

Geologist

not applicable

Spud Date

11/15/80

Date Completed

12/12/80

Total Depth

3085'

P.B.T.D.

3060'

Directional Deviation

not applicable

Oil & Gas Purchaser


Panhandle Eastern Pipeline Co.

S. 5 T. 35S R. 39 ^{XX}W

Loc. 1250' FN & EL

County Morton

640 Acres
N



Locate well correctly

Elev.: Gr. 3321'

DF 3324' KB 3325'

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	542	Common	450	3% CaCl
Production	7-7/8"	4-1/2"	10.5#	3084	Lite-wate SS Pozmix	500 150	.05% CFR-2

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement
----------	-------------	--------------

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
2	.47	2922-71' O.A.

Size	Setting depth	Packer set at
2-3/8"	3049'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
A/2000 gal 15% HCl. F/80,000 gal water, 120,000# riversand	2922-71' O.A.

INITIAL PRODUCTION

Date of first production

waiting on pipeline

Producing method (flowing, pumping, gas lift, etc.)

Flowing

RATE OF PRODUCTION
PER 24 HOURS

Oil

--

Gas

860

Water

--

Gas-oil ratio

--

CFPB

Disposition of gas (vented, used on lease or sold)

To be sold

Producing interval(s)

2922-71' O.A.

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Anadarko Production Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name LIGHT "J"	GAS
S 5 T 35 S R 39 E W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand, Clay	0'	505'		
Redbed	505'	1000'		
Redbed, Anhydrite	1000'	1908'		
Redbed, Shale	1908'	2020'		
Shale, Shale w/Lime	2020'	2206'		
Lime, Shale	2206'	3085'		
TD		3085'		
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

Date Received


 Signature
 Paul Campbell, Division Production Manager
 Title
 December 16, 1980
 Date