

8-35-39W

COMPANY ANADARKO PRODUCTION

SEC. 8 T. 35 R. 39W

FARM Rickert "A" NO. 2

LOC. C NW

1320' NSL & 1320' EWL

TOTAL DEPTH 2885

COMM. 9-27-64

COMP. 10-2-64


SHOT OR TREATED

CONTRACTOR Holm Drlg.

ISSUED 8-20-66

COUNTY Morton

KANSAS



CASING

20 10
15 8 5/8" @ 551' W/350 SX.
12 6
13 5 1/2" @ 2883' W/250 SX.

ELEVATION 3319.56' GL

PRODUCTION DEL 3851 MCF/GPD,

WH SIP 282.3#: (Hugoton
2600-2768)

FIGURES INDICATE BOTTOM OF FORMATIONS

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION

Name	From	To	No. of Shots	Gallons Used	Kind Used
Hugoton	2823	2832	36	750	15%
Hugoton	2600	2768	48	4,000	15%
				4,000	7.5%
				150,000	Water

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8-5/8"	551'	350	None
5-1/2"	2883'	250	

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Surface Sands	0	500	Lime & Shale	2605	2685
Red Bed & Shale	500	553	Lime	2685	2885
Shale	553	755	TOTAL DEPTH		2885
Shale & Gyp	755	1180			
Glorieta Sand	1180	1395	TOPS: SCOUT		
Shale & Shells	1395	1415	Herington	2560	
Shale	1415	1726	Upper Krider	2596	
Shale & Shells	1726	2010	Winfield	2662	
Shale	2010	2262	Upper Fort Riley	2732	
Shale - Lime & Chert	2262	2393	Lower " "	2799	
Lime	2393	2472			
Lime & Shale	2472	2605			

RESULTS of INITIAL PRODUCTION TEST: Deliverability Test (12-14-64) 3951 MCFD.