

State Geological Survey
WICHITA BRANCH

12-35-39 W

KANSAS DRILLERS LOG


S. 12 T. 35S R. 39 ^XE
W

API No. 15 — 189 — 20,316
County Number

Loc. 1250' FS &WL

County Stevens

640 Acres
N



Locate well correctly

Elev.: Gr. 3264.6

DF KB

Operator

Anadarko PRODUCTION COMPANY

Address

P. O. Box 351, Liberal, Kansas 67901

Well No.

Lease Name

1

COMLEY "A"

Footage Location

1250 feet from (N) (S) line 1250 feet from (E) (W) line

Principal Contractor

Geologist

Gabbert-Jones, Inc.

None

Spud Date

Total Depth

P.B.T.D.

9:45 AM 5/2/76

3070'

Date Completed

Oil Purchaser

5/25/76

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	576'	Common	550	3% CaCl
Production	7-7/8"	4-1/2"	10.5#	3070'	Lite-Wate S S Pozmix	500 150	.5% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			2 SPF	C G "B" #1	3037-47&(re-perf)
Size	Setting depth	Packer set at			
2-1/16	2938			CG "A"	2961-3020

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
A/250 Gals 15% Displaced 250 gals acid	3037-47 3037-47
A/500 gals Methanol Acid	
A/3000 gals 15% + 115 BS	2961-3020
F/w 80,000 gals wtr + 120,000# riversand	2961-3020

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
SI					
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	2747	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
SI for Pipeline Connection			2961-3020 OA Council Grove		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Anadarko Production Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Gas
Well No. 1	Lease Name COMLEY "A"	
S 12 T 256 R 39 ^K W		

WELL LOG			SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.				
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Clay-Sand	0	580		
Redbed	580	720		
Redbed-Sand	720	1392		
Redbed-Anhy	1392	1810		
Redbed-Sand	1810	2140		
Redbed-Anhy	2140	2392		
Lime-Shale	2392	3070		
Total Depth		3070		
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

Date Received	<div><i>T. W. Williams</i></div> <div>Signature</div> <div>T. W. Williams, Administrative Specialist</div> <div>Title</div> <div>July 8, 1976</div> <div>Date</div>
---------------	---