

WELL LOG BUREAU " KANSAS GEOLOGICAL SOCIETY

UNION NATIONAL BANK BLDG WICHITA, KANSAS

Plotted
H.G.
13-35-34W

Location Center SW $\frac{1}{4}$

Sec. 13 T.35 R.39W.

Drilled with Rotary and Cable.

Casing Record

County- Stevens. SEP 22 1930

10" Farm- A.E. Johnson No.1
20" 8-5/8 2490 Company- The Argus Production Co.
15 $\frac{1}{2}$ " 65/8" Contr.- Kuhn Brothers.
12 $\frac{1}{2}$ " 621 53/16" Comm.- 6-29-30 Comp.- 8-16-3Q
Total Depth 2874 Shot Quarts Between
Correspondence Regarding This Well Should Be Referred to



Figures Indicate Bottom of Formations.

Elevation Initial Production 1,520,000 G.

Date Issued. 9-20-30

Formation	Depth.
sand	480
sand and red bed broken	584
sand and red bed	600
red bed	621
red bed and gyp shells	672
gyp	730
red bed	800
red bed and gyp	1200
gyp	1225
red bed gyp	1341
gyp shale sand	1415
red bed sand	1635
gyp and shale	1725
red bed gyp	1740
broken lime red bed	1810
gyp and shale	1858
red bed gyp	1907
gyp and shale	2004
shale gyp shells	2037
red bed gyp shale	2076
red bed gyp	2100
gyp shells shale	2127
red bed gyp shells	2254
gyp shells and shale	2300
sticky shale	2328
shale and gyp shells	2391
not logged	2403
lime	2405
shale and gyp	2440
shale and broken lime	2458
broken lime	2490
lime	2495
shale blue	2530
lime	2540
shale and lime shells	2565
red rock	2570
lime	2610
shale	2625
lime	2735
red rock	2742
lime broken small sh gas	2655 2760
lime	2790
red rock	2828
lime	2874 TD.