

PT

SIDE ONE

AFFIDAVIT OF COMPLETION FORM

17-35-394 (REV) ACC-1 2nd

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: Oil, Gas, Dry, SWD, OWWO, Injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, SWD and injection, T.A.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR Anadarko Production Company

API NO. 15-129-20,599

ADDRESS P. O. Box 351

COUNTY Morton

Liberal, Kansas 67901

FIELD Panoma Council Grove

**CONTACT PERSON Mr. Paul Gatlin

PROD. FORMATION Council Grove

PHONE 316-624-6253

LEASE FITZGERALD "A"

PURCHASER Panhandle Eastern Pipe Line Company

WELL NO. 1

ADDRESS P. O. Box 838

WELL LOCATION 1250' FNL & 2590' FEL

Liberal, Kansas 67901

1250 Ft. from North Line and

DRILLING Wakefield Drilling Company

2590 Ft. from East Line of

CONTRACTOR

ADDRESS 300 West Douglas

the NE/4 SEC. 17 TWP. 35S RGE. 39W


Wichita, Kansas 67202

WELL PLAT

PLUGGING

CONTRACTOR

ADDRESS



KCC KGS (Office Use)

TOTAL DEPTH 3080 PBD 3060

SPUD DATE 1/1/82 DATE COMPLETED 3/9/82

ELEV: GR 3314' DF 3319' KB 3320'

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS

Amount of surface pipe set and cemented 605' DV Tool Used? No

AFFIDAVIT

STATE OF KANSAS, COUNTY OF SEWARD SS, I, Paul

Campbell OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS Division Operations Manager (FOR)(OF) Anadarko Production Company

OPERATOR OF THE FITZGERALD "A" LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 9th DAY OF March, 1982, AND THAT

17-35-390

SIDE TWO

WELL LOG

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Clay & Sand, Redbed	0'	606'		
Redbed	606'	750'		
Redbed, Sand streaks, Gyp	750'	1195'		
Sand	1195'	1383'		
Redbed w/Gyp streaks	1383'	1500'		
Redbed, Gyp, Anhydrite, Shale	1500'	1780'		
Redbed	1780'	2075'		
Shale & Gyp, Anhydrite streaks	2075'	2340'		
Shale & Lime	2340'	2535'		
Lime & Shale	2535'	3080'		
RTD		3080'		

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used		Depth interval treated
A/2100 gal 15% HCl + 88 BS. F/77,000 gal wtr + 116,000# riversand.		2942-92' O.A.
Date of first production SI for Pipeline	Producing method (flowing, pumping, gas lift, etc.) Flowing	Gravity
RATE OF PRODUCTION PER 24 HOURS	Oil bbis.	Gas 1684 MCF
	Water %	86 bbis. Gas-oil ratio No. CFPD
Disposition of gas (vented, used on lease or sold) To be Sold		Perforations 2942-92' O.A. Council Grove

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	605	Common	500	3% CaCl
Production	7-7/8"	4-1/2"	10.5#	3079'	Lite-wate SS Pozmix	500 150	.5% D-65

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Socks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			2	.46	2942-92' O.A.
Size 2-3/8"	Setting depth 2987'	Packer set at			

17-35-39W

KANSAS DRILLER'S LOG

LEASE: FITZGERALD "A" #1
OWNER: ANADARKO PRODUCTION COMPANY
SPUD: 1-01-82
COMP: 1-05-82

LOCATION: 1250' FNL & 2590' FEL, NE/4
SECTION 17-35S-39W
MORTON COUNTY, KANSAS
CASING: 8 5/8" SET @ 606'
4 1/2" SET @ 3079'

Clay & Sand, Red Bed	606
Red Bed	750
Red Bed, Sand streaks, Gyp	1195
Sand	1383
Red Bed W/Gyp streaks	1500
Red Bed, Gyp, Anhydrite, Shale	1780
Red Bed	2075
Shale & Gyp, Anhydrite streaks	2340
Shale & Lime	2535
Lime & Shale	3080
R.T.D.	3080

State Geologist
WICHITA, KANSAS

STATE OF KANSAS)
) ss.
COUNTY OF SEDGWICK)

I, William C. Wakefield, do hereby certify that this is a true and correct Driller's Log on the FITZGERALD "A" #1, located 1250' FNL & 2590' FEL, NE/4 Section 17-35S-39W, Morton County, Kansas, as shown by the daily drilling reports.

EARL F. WAKEFIELD, INC

By William C. Wakefield