


8- 35-40W

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, KansasCompany - CITIESSERVICE OIL CO.
Farm - Goddard "A" No. 1SEC. 8 T. 35 R. 40W
NW NW NW SE
100' S. & E. of CenterTotal Depth. 2750
Comm 2-23-51 Comp. 3-1-51
Shot or Treated.
Contractor. Barbour Drlg. Co.
Issued. 7-7-51County. Morton
KANSAS

CASING:

8 5/8" 320 cem w/200 sxs.
5 1/2" 2749 cem w/600 sxs.

Elevation. 3412

Production. 15,800,000 gas

Figures Indicate Bottom of Formations.

clay	180
sandy clay	190
shale, shells	290
red bed	395
shale, shells	650
lime	700
shale, shells	1060
lime	1100
shale, shells	1185
anhydrite	1220
shale, shells	1560
shale, lime	2405
lime	2475
shale, lime	2750
Total depth	

Tops:

Upper Krider	2522
Lower Krider	2551
Winfield	2596
Upper Ft. Riley	2671
Lower Ft. Riley	2731

Perforated:

30 shots	2524-30
50 shots	2534-44
130 shots	2550-76
100 shots	2596-2616
30 shots	2624-30
130 shots	2670-96