

State Geological Survey

KANSAS DRILLERS LOG WICHITA, BRANCH

API No. 15 — 129 — 20,215
County Number

Operator

Anadarko Production Company

Address

Box 351, Liberal, Kansas 67901

Well No.

1

Lease Name

Gerber "A"

Footage Location

1250 feet from (N) (S) line 1250 feet from (E) (W) line

Principal Contractor

Gabbert-Jones, Inc.

Geologist

Spud Date

8-7-75

Total Depth

3145'

P.B.T.D.

3020'

Date Completed

8-12-75


Oil Purchaser

S. 14 T. 35S R. 40 W

Loc. 1250' FS&WL

County Morton

640 Acres
N



Locate well correctly

Elev.: Gr. 3372.0'

DF KB

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	425'	Common	400	3% CC
Production	7-7/8"	4-1/2"	10.5#	3144'	Lite Wate Pozmix	500 150	4% gel 12½ Gilsoni .5% CFR-2

LINER RECORD

Top, ft. Bottom, ft. Sacks cement

PERFORATION RECORD

Shots per ft. Size & type Depth interval

TUBING RECORD

Size Setting depth Packer set at

SEE ATTACHED EXHIBIT "A"

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used

Depth interval treated

SEE ATTACHED EXHIBIT "A"

INITIAL PRODUCTION

Date of first production

Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION
PER 24 HOURS

Oil

bbls.

Gas

MCF

Water

Gas-oil ratio

bbls.

CFPB

Disposition of gas (vented, used on lease or sold)

Producing interval(s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Anadarko Production Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 1	Lease Name Gerber "A"	Dry Hole	
S14 T35S R40 E W			
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Surface Sand-Clay	0	390	
Redbed	390	662	
Redbed-Glorietta	662	1220	
Sand-Shale	1220	1665	
Sand-Shale-Anhy	1665	1740	
Shale-Sand	1740	2033	
Shale-Lime	2033	2330	
Lime-Shale	2330	3145	
Total Depth		3145	
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received 1975 RECEIVED STATE GEOLOGICAL SURVEY OF KANSAS	Stanley R. Shoemaker Division Office Supervisor September 22, 1975		
	Date		

EXHIBIT "A"

GERBER "A" #1
Section 14-35S-40W
Morton County, Kansas

Perforation Record - Acid, Fracture, Shot, Cement Squeeze Record

Perforated 3068-71' w/2 SPF. Acidized w/1300 gallons 15% + 12 ball sealers.

cast iron bridge plug @ 3055'.


Perforated 3032'-38' w/2 SPF. Acidized w/750 gallons 15% + 15 ball sealers.

Set cast iron bridge plug @ 3020'.

Perforated 2962'-81' w/2 SPF. Acidized w/1500 gallons 15% + 40 ball sealers.

Squeezed 2962-81' w/100 sacks Common.

Perforated 2897-2949' w/3 SPF. Acidized w/2000 gallons 15% + 110 ball sealers. Fraced
w/60,000# Riversand.


Stanley R. Shoemaker
Division Office Supervisor