

V
4-35-41W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CITIES SERVICE PETROLEUM CO.
Farm- Gore "D" No. 1

SEC. 4 T. 35 R. 41W
C NW SW

Total Depth. 5180'
Comm. 11-26-61 Comp. 12-17-61
Shot or Treated.
Contractor. Lohmann & Johnson
Issued. 4-28-62

County Morton
KANSAS



CASING:

8 5/8" 1464' cem w/725 sx.
5 1/2" 5180' cem w/400 sx.

Elevation. 3492' RB

Production. 400 BOPD/Morr
6,250,000 CFG/Top

Figures indicate Bottom of Formations.

sand, shale	593
red bed, shells	990
red bed, sand	1270
shale, lime, gyp	1453
gyp, Anhydrite	1494
shale	2000
shale, sand	2277
shale, lime	3042
lime, shale	3235
shale, chalky lime	3270
lime	3565
chalky lime	3695
lime	3791
lime, shale	3895
chalky lime	3985
lime	3997
lime, shale	4100
lime	4189
sdv lime	4247
lime, shale	4340
lime	4425
lime, shale	4448
lime, shale	4851
lime, sand	4891
lime, shale	5111
shale, sand	5155
shale, sand ?	5180
Total Depth	

TOPS: SCOUT

Topeka	3116
Gr. Lansing	3394
Heebner	3492
Toronto	3510
Lansing	3648
Marmaton	3920
Morrow	4728
Morrow Sand	4840
2nd Morrow Sand	5116
3rd Morrow Sand	5134
Keyes	5178