

90315

A-5-196

3523 KB

MAP NO. 1282 ELEV. 3521 DF

STATE Kansas COUNTY Morton SEC. 8 Twp 35 S Rge 41 W

OPERATOR Cities Service Petroleum Company LOC. C SW NE


WELL NO. 1 FARM NAME Rowland "B" FT. FROM _____ LINE _____

LOC. Wilburton, Ext. (PD 5475) FT. FROM _____ LINE _____

FR. 3-30-61 SPUD 3-28-61 COMP. 5-18-61

CONT./GEOL. Lohmann-Johnson tools

COMPLETION RECORD
 NAME PRODUCING INTERVAL FROM - TO PERF. W/HOLES TREATMENT RECORD
Topeka 3177-3276 142 9000 Ac



b _____
 c _____
 d _____

a I. P. OIL/DIST. WTR COF GAS 11,500 M.C.F.P.D. CHK. 4 pt HRS. _____

b " " " " " " " "

c " " " " " " " "

d _____

D & A ()

SIP# 416.1 FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. _____ PBDT 3316 TD 5510

CASING - CEMENT RECORD
 SIZE DEPTH W/SAX. SIZE DEPTH W/SAX.
8-5/8" 1521 150
4 1/2" 3359 200

OPERATOR Cities Service WELL NO. 1 Rowland "B" ELEV. 3523 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Topeka	3142		Topeka	3142	
Heebner	3535		Heebner	3540	
Lansing	3680		Toronfo	3558	
Marmaton	3930		Lansing	3692	
Morrow	4790		Marmaton	3927	
Morrow Sand	4890-99		Morrow	4794	
Morrow Sand	5230		Morrow Sand	5222-27	
			Keyes	5248	
			Chester	5393	
			Ste Genevieve	5455	

Spud 3-28-61. 8-5/8" @ 1521 w/150 sx.

DST # 1 (Top) 3144-3230, op 1 hr, GTS 3 mins, ga 1309 MCF/8 mins, MTS 40 mins, ga 1675 MCF/60 mins, rec 450' GCMSW, FP 270-350, SIP 475/20 mins.

DST # 2 (Morr) 4891-4920, failed.

DST # 3 (Morr) 4895-4920, op 30 mins, rec 5' M, FP 10-15, SIP 25/15 mins.

DST # 4 (Morr) 5217-63, op 1 hr, rec 630' MSW, FP 80-285, SIP 1070/30 mins.

DST # 5 (Keyes) 5287-5322, failed.

RTD 5510, logs. $4\frac{1}{2}$ " @ 3359/200 sx. MICT.
P 8/3274-76. 500 Ac. 6 hr g 2,590 MCF + 50 GWP. 1500 Ac.
20 hr ga 2,430 MCF + 3 GWP. Set BP @ 3265.
P 16/3230-34. 500 Ac. 12 hr ga 3,700 MCF + 6 GWP. 1500 Ac.
3230-34. CO 3316 g 3,290 MCF + ld.
P 82/3196-3218, 36/3177-86. g 5,400 MCF fr 3177-3276. 1000-
 $7\frac{1}{2}$ % Ac. 4000-15% Ac. 20 hr BD g 10,200 MCF. 20 min
BD g 14,800 MCF, SIP 416.

IP 4 pt COF 11,500 MCF, SIP 416.1 from Topeka 3177-3276.

LIBERAL TOPS

Topeka 3136 (+387) ϕ 11,500 MCF
Heebner 3540 (-17)
Toronto 3558 (-35)
Lansing 3692 (-169)
Marmaton 3947 (-424)
Morrow 4794 (-1271)
"S₃" Sand 5222 (-1699) 2/5
Keys 5248 (-1725) 100/113 *TMTW*
Chester 5393 (-1870)
St. Gen 5455 (-1932)
TD 5510