

6-304 W +
MAP NO. SEC. 9 TWP. 35S RGE. 41W
STATE Kan COUNTY Morton LOC. C NW NW

OPERATOR Cities Serv. Pet. Co. FT. FROM LINE

NO. 81 FARM NAME Gore "C" FT. FROM LINE

Wilburton ELEV. GR. 3523 DF 3526 KB

FR. 5/21/62 SPUD 5/20/62 COMP. 7/3/62

CONT. Lohmann-Johnson /GEOL.

NAME PRODUCING INTERVAL COMPLETION RECORD FROM - TO PERF. W/HOLES TREATMENT RECORD

a
b
c
d

d I. P. OIL/DIST. WTR. GAS M.C.F.P.D. CHK. HRS.

b " " " " " "

c " " " " " "

d

Temp Abd. D & A ()

SIP# FI TP # FI CP# SIBHP

GOR. GR. PBTD TD 5240

SIZE DEPTH CASING - CEMENT RECORD SIZE DEPTH W/SAX.

8 5/8" @ 1514 675
4 1/2" @ 3558 235

OPERATOR Cities Serv. Pet. WELL NO. 2 Gore "C" ELEV. 3526 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
-------------	-------	---------	------------	-------	---------

KB Tops & Datums

RTD(Keys) 5240 -1714

Top 3144 + 412

Shaw "A" 3268 + 258

Shaw "B" 3308 + 218

Greenwood Lans 3434 + 92

Hb 3536 - 10

Tor 3550 - 24

Lans 3684 - 158

Marm 3952 - 426

Morr 4780 -1254

Morr sd 5161-70-1635

Morr sd 5178-94-1652

Keys 5202 -1676

LTD NA

DST #1 (Shaw) 3272-3300, Op 1 hr., GTS/2", GA 698 MCFGPD/5"
Ga 1,121 MCFGPD/1 hr., R 126' GCM & 60' G&MCSW, IFP
125#, FFP 140#, FBHP 425#/15".

DST #2 (Shaw) 3310-40, Op 1 hr., R 180' sli OCM, IFP
30#, FFP 80#, FBHP 320#/30".

DST #3 (Morr) 5156-90, Op 1 hr., R 30' mud, IFP 28#.

FFP 50#, FBHP 443/30:

RTD 5240, S_j-Log, 4½" @ 3558/235 sx, CO 3520, 28/3465-72,
(Lans-Grt W) Swb 5 GWPB, NT, Nat, A/500 (15%), swb ld,
Swb 1,000 GWPB, NT, SQ/100 sx, Re-perf 32/3438-46 (Grnw-
Lans) NS, Nat, A/500 M, swb ld, swb 900 GWPB/6 hrs, PB 3340,
24/3312-18, (Shaw), A/300 M, swb 11 BW & 1 BO, NT, A/2000,
(15%), swb 25 BO + 25 BW, g 1,350 MCF/18 hrs, SQ/125 sx,
(3312-18), CO 3315, 4-way jet 3313 (Shaw), A/1000 (15%),
swb 3 BO + 29 BW/7 hrs, Temp. Abn'd.

LIBERAL ELECTRIC LOG TOPS

3524 KB

Topeka 3144 (+382)

Shawnee "A" 3268 (+258)tst 1,080 MCF + GCM + G&MCXW

Shawnee "B" 3308 (+218)tst SOCM

Greenwood Lansing 3434 (+92)

Heebner 3536 (-10)

Toronto 3550 (-24)

Lansing 3684 (-158)

Marmaton 3952 (-426)

Morrow 4780 (-1254)

"S-3" 5161 (-1635) 6/9

"S-3" 5178 (-1653) 9/16

Keyes 5202 (-1676) 24/28+

TD 5240