

8-84W

MAP NO. 82

SEC. 18-35S-41W

STATE Kansas COUNTY Morton

LOC. C SE SW

OPER Cities Service Oil Co., Guymon, Okla.

FT/FR LINE

WELL #1 FARM Barnes "B"

FT/FR LINE

WELL ~~Taloga~~

ELEV. 3570 GR. 3578 DF 3580 KB

CO. INT. Holm Drlg. tools

GEOL. Vernon Howell

INT. PTD 4700' test

F.R. 7-1-64

SPUD

7-4-64

COMP.

8-4-64

TD 4901

FM.

Morrow

PBTD

PRODUCING FM.	FROM	TO	PERF W/HOLES	TREATMENT
Morrow	4840	-50	40	Frac
Flow 804 BOPD (Gr. 38.2 deg.)				

Completion Record

8-5/8" @1544' w/600 Sx.

4½" @4900' w/150 Sx.

KB Log Tops:

Top 3128 + 452 B/Mrw sd4742 -1162

Grhw Lans3412 + 168 Mrw sd 4808 -1228

Hb 3504 + 76 B Mrw sd4858 -1278

Lans 3658 - 78 LTD 4901 -1321

Mrw 4726 -1146

Mrw sd 4736 -1156

DST #1(Mrw sd)4735-60, Op 30', R 10' M, No ISIP, IFP 35#, FFP 35#
FSIP 66#/30

DST #2(Mrw)4820-75, Op 38', GTS/3', TSTM, OTS 21', Flow to pits
for 18' R 340' gassy oil, No ISIP, IFP 792#, FFP 1149#, FSIP
1343#/30'

RTD 4901', Welex log, 4½" @4900' w 150 Sx. MICT, CO 4865', GRN Log
Pf. 40/4840-50 (Mrw) \$ 95 BO - NW, 7 hrs. Nat, \$ 52 BO-NW, 4 hrs
Frac (10,500 GO x 7000# sd)Rec 1d, 2" tbg. 4848', Flow 804 BOPD
-½" tbg. ck. GOR 300: 1, Gr. 38.2, Mrw. 4840-50, COMPLETED 7-27-
64.

Data Inc.

LIBERAL ELECTRIC LOG TOPS

3580 KB

Topeka 3128 (+452)

Greenwood/Lansing 3412 (+168)

Heebner 3504 (~~76~~)

Lansing 3658 (-78)

Swanson 3780 (-200)

Morrow 4726 (-1146)

"S-1" 4736 (-1156) 1/6

"L" Sand 4808 (-1228) 50/50 ; ϕ Flow 804 BOPD

TD 4901