


42KB

60
 MAP NO. _____ ELEV. 3490 DF
 STATE Kansas COUNTY Morton SEC. 5 TWP. 35s RGE. 41w
 OPERATOR C. S. O. LOC. C SW NE
 WELL NO. 1 FARM NAME Hoopengartner B FT. FROM _____ LINE
 OL. Wilburton NEW PAY FT. FROM _____ LINE
 FR. 4/27/60 SPUD 4/22/60 COMP. 7/7/60

CONT./GEOL. Holm Tools

COMPLETION RECORD
 NAME PRODUCING INTERVAL FROM - TO PERF. W/HOLES TREATMENT RECORD
 a Top 3090-3248 98 5000 Ac

b _____
 c _____
 d _____



COF
 I. P. OIL/DIST. WTR. GAS 17,000 M.C.F.P.D. CHK. HRS.
 b " " " " " "
 c " " " " " "
 d _____

D & A ()

SIP# 429 FI TP # _____ FI CP# _____ SIBHP _____
 GOR. _____ GR. _____ PBD 4260 TD 5381

CASING - CEMENT RECORD
 SIZE DEPTH W/SAX. SIZE DEPTH W/SAX.
 8 1471 450
 5 5153 250

OPERATOR C.S.O. WELL NO. 1 Hoopengartner ELEV. 3490 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Top	3098		Top	3087	+405
Heeb	3453		Heeb	3456	+36
Tor	3473		Tor	3476	+16
LKC	3608		LKC	3610	-118
Marm	3883		Marm	3882	390
Morr sd	4698		Chero	4364	872
Lmy sd	4815		Morr	4690	1198
S-2 sd	4980-89		sd	4/7 4840-47	1348
S-3 sd	5077-97		S-3 sd	11/29 5079-5108	1587
Keys	5130		Keys sd	4/2/19 5120-5240	1628
			Chest	5240	1748
			St Gen	5360	1868

DST 3101-76, 1 hr, gas 3 min, 1,250 MCF in 8 min, 1,850 MCF in 1 hr, 250^g gcm, FP 300-320#, BHP 460#/20.
 DST 4815-50, Fail.
 DST 4825-60, 16 min, 480ⁱ mud, FP 55-fail, BHP 110-fail.
 DST 4982-5020, 30 min, 25ⁱ mud, all 0#.
 DST 5082-5100, 1 hr, gas 40 m, 120ⁱ oily m, 360ⁱ gco, FP 50-140#, BHP 1250-1230#/30.
 DST 5125-65, 1 hr, 480ⁱ msw, FP 90-250#, BHP 1230-1100#/30.

RTD 5381, Sj, CO 5119, 28/5096-5103, SGO&W, A/500, swb 46 BO +
270 BW/8 hrs, Sq, 24/5094-5100, swb 1 BWPH, A/500, swb 12 BXWPH/
3 hrs, Sq; 20/5080-85, swb $\frac{1}{2}$ BXWPH/3 hrs, PB 4860, 12/4842-45,
swb 10 BW/3 $\frac{1}{2}$ hrs, swb $\frac{1}{2}$ BXWPH, PB 4260, 32/3240-48, g 330 MCF, 32
3227-33, g 410 MCF, A/2000, g 1,230 MCF, spray XW/20 min, 20/
3122-54, 12/3090-93, g 7,010 MCF/20 min, A/5000, g 7,440
MCF, g 9,340 MCF. COF 21,300 MCF.
¢ COF = 17,000 MCF.

LIBERAL ELECTRIC LOG TOPS

3492 KB

Topeka 3087 (+405)¢ 17,000 MCF
Heebner 3456 (+36)
Toronto 3476 (+19)
Lansing 3610 (-118)
Marmaton 3882 (=392)
Cherokee 4364 (-872)
Morrow 4690 (-1198)
"L" Sand 4840 (-1348) 4/7
"S-3" 5079 (-1587) 11/29
Keyes 5120 (-1628) 112/119; tst MXW
Chester 5240 (-1748)
Ste. Gen 5360 (-1869)
TD 5381

5696
3492
1604