

Changed to #3 Hoopigarned "C"

4-283W MAP NO. 82 SEC. 5-35S-41W
STATE Kans. COUNTY Morton LOC. C NW SE

OPER. Cities Service Oil Co., Guymon, Okla. FT./FR. _____ LINE _____

WELL #1 FARM Hoopigarned "F" FT./FR. _____ LINE _____

PROD. Wilburton ELEV. 3486 GR. 3493 DF. 3495 KB _____

TEST Holm Drlg. Tools GEOL. Bill Hetzel


INT. 5300' Oil Test

F.R. 12/16/63 SPUD. 2/18/63 COMP. 4/28/64

TD 5115 FM. Morrow sd PBTD. 5112

Completion Record	PRODUCING FM.	FROM	TO	PERF W/HOLES	TREATMENT
		<u>Morrow</u>	<u>5100 - 5111</u>		<u>44</u>

I.P. State Pot: Pump 174 BOPD, NW, Grav. 43.4 deg.



Casing Record
8-5/8" @ 1482 w/650 sx.
4 1/2" @ 5114 w/150 sx.

Data Inc.

KB Log Tops:

Top	3098	+ 397	Lans	3620	- 125	Mrw sd	5100	-1605
Hb	3465	+ 30	Marm	4216	- 721	LTD	5115	-1620
Tor	3486	+ 9	Mrw	4692	-1197	RTD	5115	-1620

in 53
C #1 (Mrw) 5065-5115, Rec. 24' sh, + 23 1/2' sd. Scatt to good oil oil show, 2' sh, 1/2' sd,

DST #1 (Mrw) 5095-5115, O, 1 hr., R 350' oil, IFP 25#, FFP 132#, FSIP 1177#/30"

RTD 5115, Welex Log, 4 1/2" @ 5114 w/150 sx., CO 5112 PBTD, 44/5100-11 (Mrw) § 30 gal. filt wtr/3 hrs w/scum oil, 500 MA, § 1d, § 2 BO + 1/2 BAW/6 hrs, Frac 8000 GO x 6000# sd, Rec 1d, § 364 BO + 19 BW/24 hrs (Grav. 41.8 deg., Gor 600-1) State Pot: P 174 BOPD NW, Grav. 43.4 deg., Mrw 5100-11, COMPLETE (4/21/64)

LIBERAL ELECTRIC LOG TOPS

3495 KB

Topeka 3098 (+397)
Heebner 3465 (+30)
Toronto 3486 (+9)
Lansing 3620 (-125)
Marmaton 4216 (-721)
Morrow 4692 (-1197)
"S-3" Sand 5100 (-1605)
TD 5115