

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

3- 35 - 42W

Company- PANHANDLE EASTERN PIPE LINE CO.

Farm- Fowler

No. 2

SEC. 3 T. 35 R. 42W

C SW $\frac{1}{4}$

1340' N SL 1385' E WL SW

Total Depth. 3215'

Comm. 9-14-57

Comp. 10-9-57


Shot or Treated.

Contractor. H & H Drlg. Co.

Issued. 1-25-58

County Morton

KANSAS



CASING:

7" 632'

5" 3215'

Elevation. 3558'

Production. 2,452,000 CFG

Figures Indicate Bottom of Formations.

sdv clay	155
sdv clay-gravel	175
sdv clay	217
sand-gravel	250
red clay	420
red clay w/rock shale	610
red bed	720
red bed-lime	975
shale-sand	1100
sand	1150
sand-shale	1340
shale	1595
shale-lime	2458
lime	2700
shale-lime	2887
lime	3215
Total Depth	

TOPS:

Wabaunsee 2684

Topeka 2877

Greenwood Lansing 3114

Perf: 3147-3156

3121-3123

2996-3022

2976-2982

2941-2946

2924-2929

Well Treatment:

A/1000 gals 15% - 10-2-57

A/1000 gals. 15% - 1-3-57