


Company- HAMILTON BROS. INC.
 Farm- J.C. Heintz No. 1

SEC. 7 T. 35 R. 42W
 C NE/4

7-35-420

County Morton

KANSAS



Total Depth. 4742'
 Comm. 11-27-59 Comp. 12-19-59
 Shot or Treated.
 Contractor Earl F. Wakefield
 Issued. 3-19-60

Elevation. 3589 RB

Production. 1,500,000 CFG

CASING:
 8 5/8" 1345'
 4 1/2" 3072'

Figures indicate Bottom of Formations.

sand	45
surface sand, clay, gyp	335
red bed	430
gypsum	460
red bed & shells	560
red bed & shale	790
broken anhydrite	830
red bed	865
red bed & anhydrite	1245
red shale	1306
anhydrite	1345
red shale & shells	1630
red shale, anhydrite stks.	1975
anhydrite	2135
red shale, & anhydrite	2270
lime	2304
shale & lime	2530
shale w/anhydrite stks.	2440
lime	2574
shale & lime	2680
lime	2835
lime & shale	3025
lime	3150
lime & shale	3203
lime & shale streaks	3303
shale & lime	3316
lime & shale	3500
lime (some chalk)	3585
lime & shale	3735
lime	3739
lime & shale	4107
lime	4143
broken lime & shale	4235
lime & shale	4456
shale & lime	4520
sand & shale	4560
shale	4615
shale	4648
lime	4742
Total Depth	

TOPS: SCOUT

Wabaunsee	2676
Elmont	2879
Topeka	2975
Lansing	3290
Cherokee	3980
Morrow	4229
Mississippi	4670