

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


10-35-42W

Company- ANADARKO PRODUCTION CO.
Farm- Barnes "B" No. 1-A

SEC. 10 T. 35 R.42W
C NE SE

al Depth. 4650'
nm. 2-28-62 Comp. 3-13-62
t or Treated.
tractor.
ied. 7-28-62

County Morton
KANSAS



Elevation. 3577' GL

Production. 286 BOPD

CASING:

8 5/8" 1432' cem w/700 sx.
4 1/2" 4647' cem w/100 sx.
2 3/8 tubing 4630'

Figures indicate Bottom of Formations.

sand 300
red bed & sand 770
red bed & gypsum 1421
Anhydrite 1433
shale & shells 2515
shale & lime 4445
sand & shale 4518
shale & shell streaks 4583
shale 4650
Total Depth

TOPS: SCOUT

Wabaunsee 2720
Topeka 2925
Gr. Lansing 3174
Lansing 3367
Marmaton 3852
Cherokee 4012
Morrow 4240
Upper Morrow Lime 4283-92
2nd Upper Morrow Lime 4296-4300
3rd Upper Morrow Lime 4480-98
Morrow "G" Sand 4614-24

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING & FRACTURING INFORMATION

NAME	FROM	TO	NO OF SHOTS	GALLONS USED	KIND USED
Morrow "G"	4617	4622	20	A/500	7½%
				F/10,000	Gelled Lease Oil