


\*\*\*

E.L. COX

State Kans com Field Greenwood  
 Company ~~.....~~ CSO County Morton  
 Farm Hall " T " No. 1  
 Sec. 2 Twp. 35 Range 42

Spot CNE, NW  
 Contractor Rine  
 Remarks ~~.....~~ MOR., Edwin COX 50%



Comm. 1-10-58 Comp. 2-12-57  
 Elev. DF 3528 GL 3520 KB 3531 TD 4591 PB  
 Pay 4534-38

I.P. f/13280.3W Press. GOR: 600:1  
 Casing Record: 13 3/8 ..... 7"  
 20" ..... 10 3/4 ..... 5 1/2" 4589/200  
 16" ..... 8 5/8 1383/450

<u>LOG</u>	<u>Sample</u>	<u>Log</u>
<u>JAN 16</u>	<u>TOP 2880</u>	<u>Wash 2674</u>
<u>8 5/8 @ 1383/450</u>		<u>TOP 2870</u>
<u>Ø 2275</u>		<u>Heep 3192</u>
		<u>Len 3310</u>
<u>JAN 29</u>		<u>Wash 3870</u>
<u>TTD 4260 new log.</u>		<u>MOR 4178</u>
<u>CSO. D. A. E. COX-will</u>		<u>S3 4532-41</u>
<u>Ø to MISS.</u>		
<u>Ø 4311 DST 4267-4311</u>		
<u>Ø P 20" rec 5' DM, FP 5-5</u>		
<u>BHP 15/15</u>		
<u>Ø 4395</u>		
<u>JAN 30</u>		
<u>33-46</u>		
<u>DST 4542-4551 Ø P 1 1/2 hrs</u>		
<u>to 70" rec 300' f/ (90'</u>		
<u>Ø 9cm + 210' oil) FP 35-70</u>		
<u>BHP 945/15</u>		
<u>RTD 4591 ran log, run pipe 5 1/2" @ 4589/200</u>		
<u>FEB 6</u>		
<u>RUCT CO? pf 16/4534-38, A/2000 sure land</u>		
<u>sure 380PH,</u>		
<u>FEB 13</u>		
<u>1 hr swab 3780, 2 hr swab 3580, 5 hrs swab 2680</u>		

11 hr test flo 13230 .3 w. FP 165 thru  
17/64" ch, gas g 79 MCF. GOR 600:1



AMARILLO TOPS

3531 KB

Topeka 2870 (+661)

Heebner 3194 (+337)

Lansing 3312 (+119)

Morrow 4176 (-645)

"S-2" 4264 (-733) T 6', por 0', NS

"S-2" 4412 (-881) T 10', por 7'

"S-3" 4532 (-1001) T 10', por 6', flo'd 10 BOPH + tr XW

Keyes 4578 (-1047) NT

TD 4582 (-1051)