

*** State Ks. Field GEOL. W.C.
 Company COLO. O&G County MORTON
 Farm HAAG No. 1
 Sec. 6 Twp. 35 Range 42
 Spot 1980' fr S & W
 Contractor Holm
 Remarks PEPL DHM, P.D. Miss
 Comm. 9-12-58 Comp. 12/10/58
 Elev. DF 3577 GL 3569 KB TD 4678 PB 2950
 Pay Top 2900 - 24 communications with
Top marks 2972 - 3000
I.P. 2.95 # Press 212 376 #
 Casing Record: 13 3/8 _____ 7"
 20" _____ 10 3/4 _____ 5 1/2" 4678/600
 16" _____ 8 5/8 1346/250



	Sample	Log	
spud, csg φ cem? SEP 2 4 DST 3095-3115 op. 2', GTS-16" Tstm, Rec. 65' GCM, FP 40-50 BHP 460/30" DST #2 3621-3715 Op. 15", Rec. 70" SGCM FP 110- BHP 630/10" losing circ	Wabr 2664 Leconpt 3088 LAN 3280 Marm 3894 FT soft 3899 Chero 4999 3949 atake 4055	Wabr 2668 Top ⁺⁶⁰⁷ 2970 ⁺³⁰² Loms 3275 Marm 3895 Chero 3941 Mor ⁻⁶²⁰ 4197 Keyes ⁻¹⁰²² 4599 Miss ⁻¹⁰⁹⁵ 4672	
	OCT 1 DST 3781-3915 op 2hr rec 1500 x wtr FP 300-750 BH 790/30 DST 4542-64 op 2hr gts in 3" 9 # 1,790 mcf/9", 2, 475 mcf/40" stat T.O.T. rec 30' hgcmt 30' hgcmt FP 85-135 BH 900/30"		

DST 4595 - 4612 op 2'

gts 1 1/2 min g 2.530 Min 10"

92,740 mcf
Ho" M w & O to ~~run~~ in T.S. / 40" rec 20' 0"
340' x wtr, FP 570-585, BHP 900/30 (440G)

RTD 4678, lgs ~~avg 3 1/2~~ / 6.39

OCT 8 DUCT CO. ~~plug to~~ ~~plug~~

OCT 15 P 4602-05 A/500 m

7' g. 1,140 mcf + 450 gwph + 30 goph
set T + plm 4579 59/55 w

C.O. 4582 P44 / 4597-58

A/500 m g. 315,000 wtr oil

Fx 16,000 x 3750 sd swb 10 BPPH

(70% Ac wtr 30% oil)

~~swabbing.~~

OCT 22 24' sub wtr 7 BOPH + 2.4 BWP

~~testg.~~

OCT 29 Sub 62 B Fid / 24' (16 B)

pl@ 3200 PA for sp 3059-60

32/300 3030 PB P36 / 2991-3000

48/2972 + 84 g 299 mcf nat.

A/500 m g 367 mcf A/1500

g 4th (wet) pl@ 2950 P16 / 2920-29

8 / 2913-15 32 / 2900-08

comm in low pres gas g 5th

w/ mix of Ac wtr H / 1500 x wtr

A/1500 (7 1/2)

NOV 5 gas g 4,737 mcf ~~testg.~~

NOV 12 ~~51 WOT~~ NOV 19

NOV 25 2 1/2' BD 10,600 mcf (wet) WOT

DEC 3 DEC 10 4th COF 2,950 mcf (wet)

31P 376.5th run 2900-24

comm with top pipe.

RTD 4678

PB 2950

✶

Morton County

6-35S-42W

Colorado Oil & Gas #1 Haag

C NE SW

3578 KB

Neva 2599 (+1029)

Topeka 2865 (+713) C 2,950 MCF

Heebner 3134 (+444)

Lansing 3294 (+284)

Morrow 4200 (-622) T 460', Tss 79'

"S-3" Sd 4542 (-964) 11/17, tst'd G, O & XW

Keyes 4598 (-1020) 58/62, tst'd G, O & XW

Chester 4660 (-1082) NT