


2-144W Map No. 82  
 OPER CITIES SERVICE OIL CO.  
 GUYMON, OKLA.  
 WELL #2 CYR 'A' (TWIN)  
 TR HOLM DRLG.  
 FIELD TALOGA FIELD (CHER, MRW)  
 I.P. CO P 29 BOPD, NW, GR 38.4 DEG  
 MRW 4554-59 API#15-129-20,001



S-T-R 2-355-42W  
 SPOT APP C SE SW  
 CO MORTON, KS.  
 ELEV 3562 KB

KB LOG:  
 TOP 2910 + 652  
 HB 3236 + 326  
 TOR 3252 + 310  
 LAN 3312 + 250  
 MAR 3746 - 184  
 MRW 4202 - 640  
 MRW SD 4440 - 878  
 MRW SD 4554 - 992  
 LTD 4562 -1000

SPUD 1-21-67 8" 1424 W/700 SX GEOL - DON HUBER

RTD 4562, SCHLUMBERGER LOG, 5½" 4561 W/100 SX  
 MICT, CO 4560, GRN LOG, PF 20/4554-59 (MRW)  
 NO SHO, NAT, 500/A (15%) MP 1800#, § LD W/ SHO OIL, 250/A  
 (15%) FRAC 7500 GAL GEL OIL + 7500# SD + 252,000 CUBIC FT CO<sup>2</sup>  
 MP 1900#, TREAT PRESS 1400#, § LD, § 14 BO/NW/13 HRS, § 29  
 BO, NW/24 HRS, GAS TSTM, (GR 38.4) POP, CO P 29 BOPD, NW,  
 (GR 38.4) MRW 4554-59 COMPLETED 2-15-67

*Data Inc*

*LD*

MISCEL DATA	GEOL	DON HUBER	ELEV	<u>3560 DF</u>	SPUD DATE	<u>1-21-67</u>
	FTG	<u>2040' FNL &amp; 600' FEL/SW/4</u>		<u>3552 GR</u>	DRLG COMP	
	SUPPT				FR by DATA	<u>1-20-67</u>
	CSG	<u>8" 1424 W/700 SX</u>	<u>5½" 4561/100 SX</u>		COMP by "	<u>2-23-67</u>