


90205

2-216W MAP NO. 82 SEC. 15-35S-42W  
 STATE Kans COUNTY Morton LOC. C NE NE  
 OPER. Petroleum Inc., Wichita, Kansas FT/FR \_\_\_\_\_ LINE \_\_\_\_\_  
 WELL 1 FARM Barnes FT/FR \_\_\_\_\_ LINE \_\_\_\_\_  
 T.L. Taloga Ext ELEV. 3581 GR. 3584 DF 3586 KB \_\_\_\_\_  
 CONT. Garvey Drlg., Tools GEOL. Doug Marden  
 CO. INT. 4900' Oil & Gas Test  
 F.R. 1-29-63 SPUD 1-28-63 COMP. 2-26-63  
 TD. 4780 FM. Ste Gen PBTD. \_\_\_\_\_



COMP. RECORD

8 5/8" @1468/615 sx. D&A  
 (KB Spl) (KB Log)

*Data Inc.*

|             |      |             |      |       |
|-------------|------|-------------|------|-------|
| Top         | 2946 | Waub        | 2750 | + 836 |
| Lans        | 3390 | Top         | 2950 | + 636 |
| Marm        | 3880 | Lans        | 3390 | + 196 |
| Chero       | 4048 | Morr sh     | 4291 | - 705 |
| Morr sh     | 4271 | U/Purdy sd  | 4332 | - 746 |
| Morr sd zn  | 4316 | U/Morr sd   | 4528 | - 942 |
| L/Purdy sd  | 4511 | Morr "G" sd | 4668 | -1082 |
| Morr "G" sd | 4648 | Keyes       | 4710 | -1124 |
| RTD         | 4780 | Ste Gen     | 4740 | -1154 |
|             |      | LTD         | 4780 | -1194 |

*Red Cave*

DST #1 (No Top) 1464-1554, Op 1 hr, WB/NT, R 360' WCM, IBHP 439#/30", IFP 114#, FFP 250#, FBHP 370#/30"  
 DST #2 (Top) 2980-3070, Op 1 hr, R 240' M, IBHP 397#/30", IFP 85#, FFP 116#, FBHP 397#/30"  
 DST #3 (Lans) 3590-3623, Op 1 hr, R 330' Salt CM + 270' MCSW IBHP 715#/30", IFP 87#, FFP 321#, FBHP 671#/30"  
 DST #4 (Morr) 4519-70<sup>52</sup>, Op 1 hr, GB R 930' M & GCSW, IBHP 1281#/30", IFP 120#, FFP 511#, FBHP 1251#/30"  
 DST #5 (Morr) 3569-3660, Op 1 hr, R 15' M, IBHP 129#/30", IFP 90#, FFP 90#, FBHP 99#/30", RTD 4780, Plugged 2-13-63  
 D&A COMPLETED (2-13-63)

LIBERAL ELECTRIC LOG TOPS

3586 KB

Topeka 2948 (+638)  
Gw/Lansing 3198 (+388)  
Heebner 3270 (+316)  
Toronto 3290 (+296)  
Lansing 3396 (+180)  
Marmaton 3796 (-210)  
Morrow 4291 (-705)  
"S<sub>1</sub>" Sand 4336 (-750) 0/8 *NT*  
"S<sub>2</sub>" Sand 4526 (-1061) 4/12 *x+w*  
"S<sub>3</sub>" Sand 4668 (-1082) 0/6 *N.T.*  
Keyes 4710 (-1124) 24/28  
Chester 4738 (-1152)  
TD 4780 D & A