


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

1-35-43W

Company- PANHANDLE EASTERN PIPE LINE COMPANY  
Farm- Harlan No. 1

SEC. 1 T. 35 R.43W  
C SW/4  
1320' N of SL & 1320'  
E of WL.  
County Morton

KANSAS



Total Depth. 3140'  
Comm. 9-19-57 Comp. 10-15-57  
Shot or Treated.  
Contractor. H & H Drilling Company  
Issued. 2-8-58

Elevation. 3594' G.L.

Production. 637,000CFG DEL

CASING:	
7"	633'
4"	3072'

Figure Indicate Bottom of Formations.	
clay & sand	640
red bed	810
Anhydrite	830
red bed & shale	910
Anhydrite	930
sand	1120
red bed	1295
shale	1580
shale & lime	1785
shale & red bed	2030
shale & sand	2235
shale & lime	2380
shale & red bed	2530
lime	2592
shale & lime	2975
lime	3140
Total Depth	

TOPS:	
Wabaunsee	2677
*Topeka	2877
Greenwood Lansing	3110

\*Producing Formation (s)

PERFORATIONS:  
2942-2950  
2902-2916

WELL TREATMENT RECORD:  
A/500 gals 15% - 10-9-57  
A/1000 gals 15% - 10-11-57  
A/1000 gals 15% - 10-13-57