

41-35-43W
CONFIDENTIAL
KCC**WELL COMPLETION REPORT AND
DRILLER'S LOG**KANSAS
State Geological Survey
WICHITA BRANCHAPI No. 15 — 129 — 20,522
County NumberS. 4 T. 35S R. 43 xE W
Loc. 990 FNL & 1650 FEL
County Morton

Operator

Anadarko Production Company

Address

P. O. Box 351, Liberal, Kansas 67901

Well No.

1

Lease Name

PENICK "A"

Footage Location

990 feet from (N) (S) line 1650 feet from (E) (W) line

Principal Contractor

KTM Drilling Company

Geologist

Mr. Jim Druyff

Spud Date

6/20/81

Date Completed

7/4/81

Total Depth

1333'

P.B.T.D.


1290'

Directional Deviation

not applicable

Oil and/or Gas Purchaser

Panhandle Eastern Pipeline Co.

Elev.: Gr. 3543.5
DF 3547.5 KB 3548.5**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24#	541'	Common	500	3% CaCl
Production	7-7/8"	4-1/2"	10.5#	1333'	Lite-wate SS Pozmix	375 150	.5% D-65 .5% D-65

LINER RECORD**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	.46 Jet	1268-84'
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
A/2000 gal 15% HCL + 40 BS	1268-84'

RELEASED

Date: JUN 30 1983

INITIAL PRODUCTION

FROM CONFIDENTIAL

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Rate of production per 24 hours	Oil	Gas	Water	Gas-oil ratio
SI for Pipeline	Flowing		-0- bbls.	391 MCF	-0- bbls.	-0- CFPB


Disposition of gas (vented, used on lease or sold)

To be Sold

Producing interval (s)

1268-84' (Red Cave)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Anadarko Production Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 1	Lease Name PENICK "A"	GAS	
S <u>4</u> T <u>35S</u> R <u>43</u> ~~Ex~~ W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Sandy Red Clay	0'	250'	
Sand, Red Clay and Rock	250'	543'	
Red Clay and Shale	543'	786'	
Red Clay, Glorietta and Anhydrite	786'	1172'	
Red Clay, Shale and Anhydrite	1172'	1333'	
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Signature Paul Campbell, Division Operations Manager Title July 9, 1981 Date		