

REVISED 6/25/81

State Geological Survey

CONFIDENTIAL

AUG

WELL COMPLETION REPORT AND
DRILLER'S LOG

WICHITA BRANCH

S. 5 T. 35 R. 43 E. W

Loc. 990' FSL & 1650' FEL

API No. 15 — 129 — 20,514
County Number

Operator

Anadarko Production Company

Address

P. O. Box 351, Liberal, Kansas 67901

Well No.

#1

Lease Name

LEWIS "D"

Footage Location

990

feet from (N) (S) line

1650

feet from (E) (W) line

Principal Contractor

KTM Drilling, Inc.

Geologist

Jim Druyff

Spud Date

5/7/81

Date Completed

5/21/81

Total Depth

1290'

P.B.T.D.

1290'

Directional Deviation

not applicable

Gas Purchaser


Panhandle Eastern Pipeline Co.

County

Morton

640 Acres

N



Locate well correctly

Elev.: Gr.

3566.1'

DF

3570.1'

KB

3571.1'

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	554'	Common	500	3% CaCl
Production	7-7/8"	4-1/2"	10.5#	1257'	Litewate SS Pozmix	350 150	D-65 D-65

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			None		
TUBING RECORD					
Size	Setting depth	Packer set at			
None					

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None	

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
SI for Pipeline		Flowing			
DATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	0 bbls.	114 MCF	0 bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
To be sold.			1285-90' Red Cave Open Hol		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Anadarko Production Company		
Well No. #1	Lease Name LEWIS "D"	Gas
S 5 T 35 R 43 ^R _W		

WELL LOG	SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.
-----------------	---

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Clay and sand gravel	0'	250'		
Red bed and rock	250'	400'		
Red clay and anhydrite	400'	550'		
Red clay and sand	550'	638'		
Red clay, anhydrite, and glor.	638'	965'		
Glor., clay, and anhydrite	965'	1236'		
Anhydrite	1236'	1257'		
Anhydrite, Silt and Sand	1257'	1290'		

RELEASED
 Date: MAY 28 1982
 FROM CONFIDENTIAL

USE ADDITIONAL SHEETS, IF NECESSARY TO COMPLETE WELL RECORD.

Date Received	<i>Paul Campbell</i> Signature
	Paul Campbell, Division Production Manager Title
	May 29, 1981 Date