

8-35-43W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ANADARKO PRODUCTION CO.
Farm- Brown "E" No. 1

SEC. 8 T. 35 R. 43W
C SW SW

Total Depth. 4400
Comm. 8-23-63 Comp. 9-8-63
Shot or Treated.
Contractor. Holm Drilling Co.
Issued. 12-28-63

County Morton
KANSAS



CASING:

8 5/8" 1317' cem w/750 sx.
4 1/2" 4393' cem w/100 sx.

Elevation. 3625.48' (H).

Production. 406 BOPD

Figures Indicate Bottom of Formations.

surface sand & clay	250
redbed & shale	790
shale & gypsum	895
sand	1018
sand & shale	1305
Anhydrite	1318
Anhydrite, shells & shale	1775
shells & shale	2215
shale	2606
lime	2815
lime & shale	3007
lime	3740
lime & shale	3885
lime	4061
lime & shale	4265
shale & sand	4400 RTD
Total Depth	

TOPS: LOG

Wabaunsee	2628
Topeka	2808
Gr. Lansing	3045
Marmaton	3476
Cherokee	3727
Morrow	4144
Upper Morrow Sand	4220