

KANSAS

8-35-43 W State Geological Survey
WICHITA, BRANCH

JAN

WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 129 — 20,461
County Number

Operator

Anadarko Production Company

Address

P. O. Box 351, Liberal, Kansas 67901

Well No.

1

Lease Name

LEWIS "A"

Footage Location

1650 feet from (N) ~~XX~~ line 1775 feet from ~~XX~~ (W) line

Principal Contractor

KTM Drilling Company

Geologist

John Jacobson

Spud Date

10/8/80

Date Completed

10/22/80

Total Depth

1357'

P.B.T.D.

1352'

Directional Deviation

not applicable

Oil and/or Gas Purchaser


Panhandle Eastern Pipe Line Co.

S. 8 T. 35S R. 43 E
Loc. 1650' FNL & 1775' FWL

County Morton

640 Acres

N



Date:

FROM ~~CONFIDENTIAL~~ correctly
3583.2

Elev.: Gr.

DF 3587.2 KB 3588.2

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	375'	Common	425	2% CaCl
Production	7-7/8"	4-1/2"	10.5#	1356'	Lite-wate SS Pozmix	120 150	.5% D-31

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	.41	1292-1304'
Size	Setting depth	Packer set at			
2-3/8"	1285'				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
A/750 gals 7.5% acid + 35 BS	1292-1304'

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
SI for pipeline connection	Flowing				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	214	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		
To be sold			1292-1304'		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Anadarko Production Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name LEWIS "A"	GAS
S 8 T 35S R 43 E W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand and Clay	0'	200'	LOGS:	
Shale, Redbed	200'	375'	WELEX	
Shale, Redbed	375'	1290'	GAMMA-GUARD LOG	
Shale and Sand Stone	1290'	1304'		
Anhydrite	1304'	1357'		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Signature Paul Campbell, Division Production Manager Title October 22, 1980 Date
---------------	--