

REVISED 6/25/81

8-35-43W

AUG


WELL COMPLETION REPORT AND
DRILLER'S LOG**CONFIDENTIAL**KANSAS
State Geological Survey
WICHITA BRANCH

S. 8 T. 35S R. 43 W

Loc. C NE/4

County Morton

640 Acres



Elev.: Gr. 3598'

DF 3602' KB 3603'

API No. 15 — 129 — 20,513
County Number

Operator

Anadarko Production Company

Address

P. O. Box 351, Liberal, Kansas 67901

Well No.

3

Lease Name

MOORE "C"

Footage Location

1320 feet from (N) XSM line

1320 feet from (E) XSM line

Principal Contractor

KT & M Drilling Company

Geologist

Mr. Jim Druryff

Spud Date

5/4/81

Date Completed

5/15/81

Total Depth

1326'

P.B.T.D.

1326'

Directional Deviation

not applicable

Oil and Gas Purchaser

Panhandle Eastern Pipe Line Co.

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	558	Common	500	3% CaCl
Production	7-7/8"	5-1/2"	14#	1293	Lite-wate SS Pozmix	350 150	.5% D-65 .5% D-65

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
NONE	

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
SI for Pipeline		Flowing			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	--	147	--	--	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
To be sold			Red Cave (Open Hole) 1323-1326'		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

CONFIDENTIAL

Operator

Anadarko Production Company

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.

3

Lease Name

MOORE "C"

GAS

S 8 T 35S R 43 K
W**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

Sand & Red Clay
Red bed & Clay
Red Shale & Glorietta
Shale & Anhydrite
Anhydrite, Silt and Sand

0'	410'
410'	867'
867'	1178'
1178'	1293'
1293'	1326'

RELEASED

Date: MAY 28 1982

FROM CONFIDENTIAL

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature

Paul Campbell, Division Production Manager

Title

May 20, 1981

Date