

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


10-35-43W

Company- PANHANDLE EASTERN PIPE LINE CO.
Farm American Life No. 1

SEC. 10 T. 35 R. 43W
NE NE SW
2375' fr NL, 2490' fr WL

County Morton
KANSAS

Total Depth. 3135
Comm. 9-29-55 Comp. 10-5-55
Shot or Treated. 2000 gals. 15% acid
Contractor. Musgrove Petroleum Corporation
Issued. 12-24-55



Elevation. 3630.24

Production. 4,732,000 CFGPD
RP 420#

CASING:

8 5/8 @ 594' w/ 300 sx cmt.
5 1/2 @ 3110' w/ 300 sx cmt.

Figures indicate Bottom of Formations.

sand & shale streaks	252
blue shale	300
red bed	345
sand & shale	595
red bed, shale & shells	905
anhydrite	928
shale, shells & sand	1230
shale & shells	1865
shale & lime	2985
lime	3135
Total Depth	

TOPS:

Wabaunsee	2657
Topeka	2855
Lansing	3086

Perforated: 2996-3003, 2988-92, 2980-84,
2964-68; 2953-60, 2922-27, 2902-04,
2891-96, 2879-84.