

15-129-20333

State Geological Survey
KANSAS DRILLERS LOG WICHITA BRANCH

S. 10 T. 35S R. 43 K W

Loc. C SW/4

County Morton

API No. 15 — 129 — 20,333
County Number

Operator

ANADARKO PRODUCTION COMPANY

Address

P. O. BOX 351, LIBERAL, KANSAS 67901

Well No.

Lease Name

1 AMERICAN LIFE "A"

Footage Location

1250 feet from $\frac{1}{4}$ (S) line

1250 feet from $\frac{1}{4}$ (W) line

Principal Contractor

Geologist

Gabbert-Jones, Inc.

None

Spud Date

Total Depth

P.B.T.D.


10/1/77

1425'

1398'

Date Completed

Oil Purchaser



Locate well correctly

Elev.: Gr. 3644.9

DF KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20	404'	Common	300	3% CaCl
Production	7-7/8"	4-1/2"	10.5	1425'	Lite Wate	200	4% gel
					Salt Sat Poz	150	0.05% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	Hyper II	1386-1402'
			2	McCullough	1386-91'


ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Squeeze cemented w/100 sxs Common	1386-1402'
500 gals Acetic Acid + 1,000 gals 7-1/2% Fe Acid	1386-91'

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
Non-productive	Swab Test 10/29/77
RATE OF PRODUCTION PER 24 HOURS	Oil Gas Water Gas-oil ratio
	0 bbls. TSTM MCF 6BPH bbls. CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval(s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator ANADARKO PRODUCTION COMPANY		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: DRY HOLE	
Well No. 1	Lease Name AMERICAN LIFE "A"		
S 10 T 35S R 43 Ex W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Surface Clay-Sand-Redbed	0'	405'	Welex
Redbed	405'	793'	Fracture Finder
Redbed-Anhy-Sand	793'	1365'	Micro-Seismo-
Anhydrite	1365'	1425'	gram Log
TOTAL DEPTH		1425'	400-1421'
PBSD		1398'	Welex
			Acoustic
			Velocity Gamma
			Caliper Log
			400-1422'
			Schlumberger
			Perforating
			Depth Control
			900-1423'
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Signature Paul Campbell, Division Production Manager Title April 12, 1978 Date		