

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas

17-35-43W

Company. PAN AMERICAN PETROLEUM CORPORATION
Farm. Brooks Gas Unit No. 1

SEC. 17 T. 35 R. 43W

C E/2 SW NE

3300' N of SL 3630' E of WL

Total Depth. 4730

PBTD 4720

Comm. 1-17-57

Comp. 2-12-57


Shot or Treated.

Contractor.

Issued. 8-3-57

County Morton

KANSAS



CASING:

8 5/8 @ 1300' w/ 1000 sx cmt.

5 1/2 @ 4728' w/ 400 sx cmt.

Elevation. 3678 DF

Production. 6,146,000 CFGPD
4 BOPD

Figures indicate Bottom of Formations.

sand	300
red bed	455
red bed & shale	860
red bed & anhydrite	1275
anhydrite	1300
shale	1700
shale & lime	2005
anhydrite	2130
lime & shale	2988
lime	3045
lime & shale	3120
lime	3330
shale & lime	4114
lime	4210
lime & shale	4730
Total Depth	

Plugged back to 4720

TOPS:

Atoka	3937
Morrow shale	4177
Purdy	4280
Keyes sand	4592
Mississippian	4692

Core #1: 4269-99, rec. 28 1/2'

Core #2: 4299-4322, rec. 23'

DST #1: 4296-4322, open 30 min. gas
to surf. 2 min. gauged 3120 MCF/15
min. 3400 MCF/30 min. rec. 180' free
oil IFP 290#, IHH 2050#, FHH 1960#
BHP 1320#

Ran Schlumberger Gamma Ray, Micro-
log & Microcaliper Surveys.