

REC'D

MAY 30 1974

14-35 ~~43~~ W
43

S. 14 T. 35 R. 43 ~~E~~ W

Loc. C SW SW

County Morton

API No. 15 — 129 — 20,153
County Number

DIST. COMP.

Operator
Texaco, Inc.

Address P. O. Box 2420 Tulsa, Oklahoma


Well No. Tr. #1-3 Lease Name CNEMW "A" Unit

Footage Location
660 feet from (N) (S) line 660 feet from (E) (W) line

Principal Contractor Rains & Williamson Geologist

Spud Date 7/2/74 Total Depth 4404' P.B.T.D. 4366'

Date Completed 8/11/74 Oil Purchaser Derby



Elev.: Gr. 3629'

DF 3634' KB 3637'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface	12 1/4"	8-5/8"	24#	1430	poz reg	600 150	3% CaCl
production		5 1/2"	15 1/2#	4403	poz	100 *	
[* thru DV @ 2938' w/125 sx 50/50 poz.]							

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	jts	4255-69'

Size	Setting depth	Packer set at
2-3/8"	4209'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
A/1500 gal 15% MA	4255-69'
Frac w/10 x 10 sd gelled SW	"

INITIAL PRODUCTION

Date of first production <u>7-29-74 [swab test]</u>	Producing method (flowing, pumping, gas lift, etc.) <u>Pmpg.</u>
RATE OF PRODUCTION PER 24 HOURS	Oil <u>154</u> bbls. Gas <u>-0-</u> MCF Water <u>Trace</u> bbls. Gas-oil ratio <u>CFPB</u>
Disposition of gas (vented, used on lease or sold)	Producing interval (s) <u>4255-69'</u>

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

TEXACO INC.

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

OIL

Well No.

Tr. 1 #3

Lease Name

CNEMW "A" UNIT

S 14 T 35 S R 43 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sd & Clay	0	155	FDC	2909-4403'
Clay & Red Bed	155	500	IES	1430-4398'
Sd, Clay & Red Bed	500	826		
Red Bed	826	1045		
Red Bed & Anhyd	1045	1109		
Sh & Anhyd	1109	1310		
Anhyd & Sh	1310	1431		
Red Bed & Sh	1431	2090		
Sh & Li	2090	2266		
Ei & Sh	2266	4400		
Li	4400	4551		
TD	4551			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



F. E. Anderson
 F. E. ANDERSON Signature
 Oper. Supt. Title
 September 19, 1974 Date